


DATA SERIES

IOGP Safety performance indicators - 2025 data



Acknowledgements

IOGP would like to thank those companies that have participated in the data collection programme. This Report was produced by the Safety Committee.

Feedback

IOGP welcomes feedback on our reports: publications@iogp.org

Disclaimer

Whilst every effort has been made to ensure the accuracy of the information contained in this publication, neither IOGP nor any of its Members past present or future warrants its accuracy or will, regardless of its or their negligence, assume liability for any foreseeable or unforeseeable use made thereof, which liability is hereby excluded. Consequently, such use is at the recipient's own risk on the basis that any use by the recipient constitutes agreement to the terms of this disclaimer. The recipient is obliged to inform any subsequent recipient of such terms.

Please note that this publication is provided for informational purposes and adoption of any of its recommendations is at the discretion of the user. Except as explicitly stated otherwise, this publication must not be considered as a substitute for government policies or decisions or reference to the relevant legislation relating to information contained in it.

Where the publication contains a statement that it is to be used as an industry standard, IOGP and its Members past, present, and future expressly disclaim all liability in respect of all claims, losses or damages arising from the use or application of the information contained in this publication in any industrial application.

Any reference to third party names is for appropriate acknowledgment of their ownership and does not constitute a sponsorship or endorsement.

Copyright notice

The contents of these pages are © International Association of Oil & Gas Producers. Permission is given to reproduce this report in whole or in part provided (i) that the copyright of IOGP and (ii) the sources are acknowledged. All other rights are reserved. Any other use requires the prior written permission of IOGP.

These Terms and Conditions shall be governed by and construed in accordance with the laws of England and Wales. Disputes arising here from shall be exclusively subject to the jurisdiction of the courts of England and Wales.

DATA SERIES

IOGP Safety performance indicators - 2025 data

Revision history

VERSION	DATE	AMENDMENTS
1.00	June 2026	First release

Table of contents

Contributing companies

Introduction and background

Scope of reporting and data validation

Data series

1. Summary of 2025 results

1.1 General

1.2 Fatalities

1.3 Total recordable injuries

1.4 Lost time injuries

2. 2025 results

2.1 Fatalities

2.2 Fatal accident rate (FAR)

2.3 Fatal incident rate (FIR)

2.4 Fatalities by incident cause and activity

2.5 Total recordable injury rate (TRIR)

2.6 Lost time injury rate (LTIR)

2.7 Lost work day case causes and activities

2.8 Severity of lost work day cases

2.9 Severity of restricted work day cases

2.10 Incident triangles

2.11 Causal factors

2.12 Fatal Incident Causal Factors

2.13 High Potential Event Causal Factors

2.14 Life-Saving Rules

3. Results by region

3.1 Fatalities

3.2 Fatal accident rate (FAR)

3.3 Total recordable injury rate (TRIR)

3.4 Lost time injury rate (LTIR)

3.5 FAR, TRIR, and LTIR five-year rolling averages

3.6 Severity of lost work day cases

3.7 Individual country performance

3.8 Incident triangles by region

4. Results by function

4.1 Fatalities

4.2 FAR, TRIR, and LTIR five-year rolling averages

4.3 Severity of lost work day cases (LWDC)

4.4 Exploration performance

4.5 Drilling performance

4.6 Production performance

4.7 Construction performance

4.8 Unspecified performance

5. Results by company

5.1 Overall company results

5.2 Company results by function

Appendix A – Database dimensions

Proportion of database used in analysis

Appendix B – Data tables

Section 1 Summary

Section 2 Overall results - fatalities

Section 2 Overall results - injuries

Section 3 Results by region

Section 4 Results by function

Section 5 Results by company

Appendix C – Contributing companies

Appendix D – Countries represented

Appendix E – Glossary of terms

Contributing companies

The safety statistics were derived from data provided by the following companies:

2023

ADDAX Petroleum Limited
ADNOC
Aker BP
Azule
Bapco Energies
Basrah Gas Company
Beach Energy
BP
BW Energy
Capricorn Energy
CCED
Cenovus
CEPSA EP
Chevron
CNOOC
ConocoPhillips
Crescent Petroleum
Dana Gas
Dolphin Energy
ENI
Equinor ASA
ExxonMobil
Genel Energy
Gulf Keystone
Harbour Energy
Hess Corporation
INPEX Corporation
KMG
Kosmos Energy
Kuwait Oil Company
MOL
Neptune Energy
North Oil Company
OMV
ONGC
Orlen
Oxy
Pan American Energy
Petrobras
Petronas Carigali Sdn Bhd
Pluspetrol
Prime Energy
PTTEP
QatarEnergy
QatarEnergy LNG
Repsol
Shell Companies
SOCAR
Sonangol
Spirit Energy
Suncor
TotalEnergies
Trident Energy
Tullow Oil
Vår Energy
Wintershall Dea
Woodside
YPF SA

2024

ADDAX Petroleum Limited
ADNOC
Aker BP
Apache
Assala Energy
Azule
Bapco Energies
Basrah Gas Company
Beach Energy
BP
Capricorn Energy
CCED
Cenovus
Chevron
CNOOC
ConocoPhillips
Crescent Petroleum
Dana Gas
Dolphin Energy
ENI
Equinor ASA
ExxonMobil
Gulf Keystone
Harbour Energy
Hess Corporation
INPEX Corporation
Kosmos Energy
Kuwait Oil Company
MOL
North Oil Company
OMV
ONGC
Orlen
Oxy
Pan American Energy
PEMEX
Perenco
Pertamina
Petrobras
Pluspetrol
Prime Energy
Prio
PTTEP
QatarEnergy
QatarEnergy LNG
Repsol
Shell Companies
SOCAR
Sonangol
Spirit Energy
TotalEnergies
Trident Energy
Tullow Oil
Vår Energy
Woodside
YPF SA

2025

ADDAX Petroleum Limited
ADNOC
Aker BP
Assala Energy
Azule
Bapco Energies
Basrah Gas Company
BP
Brunei Shell
BW Energy
CCED
Cenovus
Chevron
ConocoPhillips
Crescent Petroleum
Dana Gas
Dolphin Energy
ENI
Equinor ASA
ExxonMobil
Gulf Keystone
Harbour Energy
INPEX Corporation
Ithaca Energy
KMG
Kosmos Energy
Kuwait Oil Company
MOL
North Oil Company
OMV
ONGC
Orlen
Oxy
Pan American Energy
PEMEX
Perenco
Pertamina
Petrobras
Petronas Carigali Sdn Bhd
Pluspetrol
Prime Energy
Prio
PTTEP
QatarEnergy
QatarEnergy LNG
Renaissance
Repsol
Shell Companies
SOCAR
Sonangol
Spirit Energy
TotalEnergies
Trident Energy
Tullow Oil
Vår Energy
Woodside

Introduction

The International Association of Oil and Gas Producers (IOGP) has been collecting safety incident data from its Member Companies globally since 1985. The data collected are entered into the IOGP safety database, which is the largest database of safety performance in the upstream industry.

The principal purpose of the data collection and analysis is to record the global safety performance of the contributing IOGP Member Companies on an annual basis. The submission of data is voluntary and is not mandated by IOGP Membership. The annual reports provide trend analysis, benchmarking, and the identification of areas and activities on which efforts should be focused to bring about the greatest improvements in performance.

The IOGP incident reporting system covers worldwide upstream operations, both onshore and offshore, and includes incidents involving both Member Companies and their contractor employees.

The key indicators presented are:

- number of fatalities
- fatal accident rate
- fatal incident rate
- total recordable injury rate
- lost time injury rate
- number of lost work day cases
- number of lost work days
- number of restricted duty cases
- restricted duty days
- number of medical treatment cases

The analysis presents contributing IOGP Members' global results for these indicators, which are then analysed by region, function, and company. A code is used to preserve the anonymity of the reporting company, which will typically report its own data as well as that of its associated contractors (see [Appendix C](#)).

In 2010, data collection was initiated to capture 'causal factors' associated with fatal incidents and high potential events. These data are presented in [section 2.11 of this Report](#). Wherever practicable, results are presented graphically.

The data underlying the charts are presented in [Appendix B](#). The causal factors and chart data are available in editable format to logged in IOGP Members within the data website at <https://data.iogp.org/>.

Narrative descriptions for fatal incidents and selected high potential events with valuable learning that were reported by participating IOGP Member Companies can be found at <https://data.iogp.org/Safety/FatalIncidents> and <https://data.iogp.org/Safety/HighPotentialEvents> respectively.

Scope of reporting and data validation

The data requested from participating IOGP Member Companies are published in an annual User Guide, which contains definitions and the scope of the safety data submission. This document is available from the data website at <https://data.iogp.org/Safety/UserGuide> and the IOGP publications library at <https://www.iogp.org/bookstore/>.

The safety data submission process is used for the collection of information relating to safety performance, process safety performance, and motor vehicle crashes. The IOGP safety database has built-in validation requirements and each company submission is validated by the IOGP Secretariat and the work group (Safety Committee, Subcommittee, or Expert Group) responsible for the data set in accordance with the IOGP data

collection and reporting procedure. Any communication with reporting companies is conducted by the IOGP Secretariat and any data validated by an IOGP work group is blind coded to preserve the anonymity of the reporting companies.

A self-assessment questionnaire is included within the data submission process to determine the alignment between the requested information and the company submissions. The information provided in this questionnaire is also used in the validation process. Data that appear to be incorrect and that cannot be confirmed by the submitting company as correct may be excluded from the data set at the discretion of the Secretariat.

Notable changes to the data request include:

- The number of permanent impairment injuries and narratives were added in 2023 and results were first published in 2024 (Report 2023f, *Safety performance indicators – Fatality and permanent impairment injuries (FPI) – 2022-2023 data*).
- The fatal incident activity category “Excavation, trenching, ground disturbance” was added in 2019.
- The incident cause category of “Dropped objects” was added in 2018. The categories “Caught in, under or between” and “Struck by” were modified to exclude dropped objects.
- The incident cause category of “Aviation Accident” was introduced in 2016. Aviation accidents were previously included in the “Other” incident category.

The scope of data included within this Report is detailed in this section.

Data series

Other IOGP Data Reports published annually include:

- Aviation safety data.
- Environmental performance indicators.
- Fatality and permanent impairment injury data.
- Health performance indicators.
- Motor vehicle crash data.
- Process safety event data.

These are available from the IOGP website <http://www.iogp.org/bookstore>, and in electronic format in IOGP's data website at <https://data.iogp.org/>.

1. Summary of 2025 results

This section summarizes the safety performance of contributing IOGP Member Companies for 2025.

The key performance indicators (KPI) used to benchmark safety performance in this section are:

- number of fatalities
- fatal accident rate (FAR)
- total recordable injury rate (TRIR)
- lost time injury rate (LTIR)

Third party fatalities are not included in this analysis.

Definitions

Fatal accident rate (FAR):

The number of company/contractor fatalities per 100 million hours worked.

Total recordable injury rate (TRIR):

The number of recordable injuries (fatalities + lost work day cases + restricted work day cases + medical treatment cases (MTC)) per million hours worked. Note when MTC or RWDC are not reported by a company for a country the associated work hours, fatalities, lost work day cases, restricted work day cases and medical treatment cases are excluded from TRIR calculations.

Lost time injury rate (LTIR):

The number of lost time injuries (fatalities + lost work day cases) per million hours worked.

1.1 General


The safety performance of contributing IOGP Member Companies in 2025 is based on the analysis of 3,855 million work hours of data.

Submissions were made by 56 of the 72 operating company IOGP Members.

The data reported cover operations in 87 countries.

The resulting fatal accident rate (FAR) was 1.35, 75% higher than last year's figure (0.77).

Figure 1



1.2 Fatalities

Against the background of a 7% decrease in work hours reported, the number of fatalities has increased from 32 in 2024 to 52 in 2025. The 52 fatalities occurred in 40 separate incidents. The resulting fatal accident rate (FAR) was 1.35, 75% higher than last year's figure (0.77). The company and contractor FAR were 0.88 and 1.49 respectively. Onshore and offshore FAR were 1.34 and 1.37 respectively.


Each reported fatal incident is allocated a work activity and cause. With regard to the cause, 17% of the fatalities reported in 2025 were the result of incidents categorized as 'Caught in, under or between (excl. dropped objects)' (9 fatalities in 6 separate incidents).

Fatalities categorized as 'Struck by (not dropped object)' accounted for 15% of the fatalities, with 8 fatalities in 7 separate incidents.

Fatalities categorized as 'Dropped objects' also accounted for 15% of the fatalities, with 8 fatalities in 8 separate incidents.

One land transport incident that was security related claimed the lives of 4 people.

Figure 2




With regard to the activity, 27% of the fatalities reported in 2025 were the result of incidents categorized as 'Maintenance, inspection, testing' (14 fatalities in 11 separate incidents).

Fatalities categorized as 'Transport - Land' accounted for 19% of the fatalities, with 10 fatalities in 4 separate incidents.


9 fatalities were reported in 8 separate incidents in the 'Drilling, workover, well operations' activity, and 6 fatalities were reported in 6 separate incidents in the 'Lifting, crane, rigging, deck operations' activity.

Figure 3



The FAR for 2025 was 1.35, 75% higher than the 2024 rate (0.77). The company-only FAR for 2025 was 0.88, 54% higher than the rate for 2024 (0.57). The contractor-only FAR was 1.49, 77% higher than the rate for 2024 (0.84).


Figure 4



1.3 Total recordable injuries

The overall total recordable injury rate (TRIR) (fatalities, lost work day cases, restricted work day cases, and medical treatment cases) was 0.76, 6% lower than in 2024 (0.81).


Figure 5:



1.4 Lost time injuries

The overall lost time injury rate (LTIR) (fatalities and lost work day cases) was 0.25, 4% higher than in 2024 (0.24).

Figure 6:



The participating IOGP Member Companies reported 916 lost work day cases (LWDC) (injuries resulting in at least one day off work):

- 713 incidents were contractor related.
- 203 incidents were company related.

Participating companies reported 29,703 days of work lost through injuries.

Figure 7 shows the percentage of LWDC by cause.

- 195 cases, 21% of the total, were categorized as 'Slips and trips (at same height)': 2024 results showed 206 cases, accounting for 22% of the total.
- 'Caught in, under or between (excl. dropped objects)' accounted for 154 cases, 17% of the total (189 cases, 20% of the total in 2024).
- 'Struck by (not dropped object)' accounted for 138 cases, 15% of the total (148 cases, 16% of the total in 2024).

Figure 7:





Figure 8 shows the percentage of LWDC by activity.

- 173 cases, 19% of the total, were categorized as 'Maintenance, inspection, testing': 2024 results showed 177 cases, accounting for 19% of the total.
- 'Production operations' accounted for 150 cases, 16% of the total (154 cases, 16% of the total in 2024).
- 'Drilling, workover, well operations' accounted for 144 cases, 16% of the total (190 cases, 20% of the total in 2024).

Figure 8:



See [Appendix B - Section 1](#) for data tables.

2. 2025 results

In this section, the primary indicators used to measure contributing IOGP Member Companies’ safety performance are:

- number and nature of fatalities
- total recordable injury rate
- fatal accident rate
- fatal incident rate
- lost time injury rate

Third party incidents are not included in this Report.

2.1 Fatalities


Table 1: Number of fatalities (2024 and 2025)

Company/contractor	2024			2025		
	Onshore	Offshore	Overall	Onshore	Offshore	Overall
Company	4	2	6	4	4	8
Contractor	13	13	26	35	9	44
OVERALL	17	15	32	39	13	52

52 company and contractor fatalities were reported in 2025. This is 20 more than were reported in 2024 and 25 more than in 2023.

The 52 fatalities occurred in 40 separate incidents.

Figure 9:



2.2 Fatal accident rate

In 2025 there were 8 company fatalities (6 in 2024) as a result of 8 separate incidents.


In 2025 there were 44 contractor fatalities (26 in 2024) as a result of 32 separate incidents.

Table 2: Fatal accident rate (2024 & 2025)

	Fatal accident rate (FAR)		Relative to 2024 FAR
	2024	2025	
Onshore	0.56	1.34	139% higher
Offshore	1.31	1.37	5% higher
OVERALL	0.77	1.35	75% higher
Company	0.57	0.88	54% higher
Contractor	0.84	1.49	77% higher


All hours in the database were used for calculations of fatal accident rate (FAR).

Figure 10:



The difference between the onshore and offshore FAR displays a large variation over the 10-year period shown in Figure 11. Neither is consistently lower. This is generally attributable to single "transportation", "fire and explosion", or "assault/violent act" incidents involving high numbers of fatalities.

Figure 11:



2.3 Fatal incident rate

The fatal incident rate (FIR) is a measure of the rate at which fatal incidents occur, in contrast to the fatal accident rate (FAR) which measures the rate of fatalities. Accordingly, for company and contractor fatalities, the FIR will be less than or equal to the FAR. Comparison of FAR and FIR gives an indication of the magnitude of the incidents in terms of lives lost.

Overall, the FIR increased by 108% compared with last year (40 fatal incidents in 2025, 21 fatal incidents in 2024).

All hours in the database were used for calculations of FIR.

Table 3: Fatal incident rate (2024 & 2025)

	Fatal incident rate (FIR)		Relative to 2024 FIR
	2024	2025	
Onshore	0.47	1.03	119% higher
Offshore	0.61	1.05	72% higher
OVERALL	0.50	1.04	108% higher
Company	0.57	0.88	54% higher
Contractor	0.48	1.09	127% higher

Figure 12:




Figure 13:





Figure 14:



2.4 Fatalities by incident cause and activity

35 of the 40 fatal incidents involved one fatality. 5 incidents involved 2 or more fatalities.

Table 4: Fatalities by cause and activity (2025)

Activity	Cause													
	Assault or violent act	Aviation accident	Caught in, under or between (excl. dropped objects)	Confined space	Cut, puncture, scrape	Dropped objects	Explosions or burns	Exposure electrical	Exposure noise, chemical, biological, vibration	Falls from height	Overexertion, strain	Pressure release	Slips and trips (at same height)	Struck by (not dropped object)
Construction, commissioning, decommissioning						1		1						1
Diving (incl. decompression), subsea, ROV														
Drilling, workover, well operations			1			2				2				4
Excavation, trenching, ground disturbance														
Lifting, crane, rigging, deck operations			1			4								1
Maintenance, inspection, testing			2			1	5	1	1	2				1
Office, warehouse, accommodation, catering														
Production operations							1			1				2
Seismic/survey operations														1
Transport - Air		3												
Transport - Land	4		5											1
Transport - Water, incl. marine activity														
Unspecified - other														1
OVERALL	4	3	9			8	6	2	1	5				8

Figure 15:

Number of fatalities by cause (2025)




Figure 16:




Table 5: Fatalities by cause (2021 - 2025)

Cause	Number of fatalities				
	2021	2022	2023	2024	2025
Assault or violent act	6	1	8	4	4
Aviation accident	0	1	0	1	3
Caught in, under or between (excl. dropped objects)	6	6	4	2	9
Confined space	0	0	0	1	0
Cut, puncture, scrape	0	0	0	0	0
Dropped objects	0	6	1	1	8
Explosion, fire or burns	0	4	5	13	6
Exposure electrical	1	0	1	2	2
Exposure noise, chemical, biological, vibration, extreme temperature	0	1	2	0	1
Falls from height	4	3	1	3	5
Overexertion, strain	0	0	0	0	0
Pressure release	0	4	1	0	0
Slips and trips (at same height)	0	0	0	0	0
Struck by (not dropped object)	2	6	2	4	8
Water related, drowning	1	1	2	1	4
Unspecified - Other	0	0	0	0	2
OVERALL	20	33	27	32	52

Figure 17:





Table 6: Fatalities by activity (2021 - 2025)

Activity	Number of fatalities				
	2021	2022	2023	2024	2025
Construction, commissioning, decommissioning	3	4	3	4	4
Diving (incl. decompression), subsea, ROV	0	1	0	0	0
Drilling, workover, well operations	2	9	3	11	9
Excavation, trenching, ground disturbance	0	1	0	0	0
Lifting, crane, rigging, deck operations	2	4	2	2	6
Maintenance, inspection, testing	5	3	4	3	14
Office, warehouse, accommodation, catering	0	0	0	0	0
Production operations	0	5	7	7	5
Seismic/survey operations	0	1	0	0	0
Transport - Air	0	1	0	1	3
Transport - Land	7	3	7	4	10
Transport - Water, incl. marine activity	1	0	1	0	0
Unspecified - other	0	1	0	0	1
OVERALL	20	33	27	32	52

Figure 18:



2.5 Total recordable injury rate

Submissions without information on medical treatment cases (MTC) were filtered out, leaving a dataset of 3,535 million hours, 92% of the database. There were 2,685 reported recordable injuries (fatalities + LWDC + RWDC + MTC where MTC are reported), which equates to an average of 51 recordable injuries every week of the year or more than 7 injuries every day of the year. See [Appendix A – Database dimensions](#).

An overall decrease in total recordable injury rate (TRIR) of 6% is seen in 2025.

Table 7: Total recordable injury rate (2024 & 2025)

	Total recordable injury rate (TRIR)		Relative to 2024 TRIR
	2024	2025	
Onshore	0.73	0.62	15% lower
Offshore	1.04	1.19	14% higher
OVERALL	0.81	0.76	6% lower
Company	0.56	0.61	9% higher
Contractor	0.89	0.80	10% lower

Figure 19:





Figure 20:



2.6 Lost time injury rate

There were 916 reported lost work day cases resulting in at least one day off work, which equates to an average of 17 injuries resulting in at least one day off work every week of the year or 3 injuries every day of the year.

For calculations of lost time injury rate (LTIR), all hours in the database were used. See [2.8 Severity of lost work day cases](#) for further information on lost work day case severity.

Table 8: Lost time injury rate (2024 & 2025)

	Lost time injury rate (LTIR)		Relative to 2024 LTIR
	2024	2025	
Onshore	0.18	0.18	No change
Offshore	0.39	0.46	18% higher
OVERALL	0.24	0.25	4% higher
Company	0.21	0.23	10% higher
Contractor	0.24	0.26	8% higher

Figure 21:





Figure 22:



2.7 Lost work day case causes and activities

Table 9: Lost work day cases by cause (2025)


Cause	Number	% of total
Assault or violent act	3	0.3
Caught in, under or between (excl. dropped objects)	154	16.8
Cut, puncture, scrape	37	4.0
Dropped objects	29	3.2
Explosion, fire or burns	56	6.1
Exposure electrical	8	0.9
Exposure noise, chemical, biological, vibration, extreme temperature	36	3.9
Falls from height	56	6.1
Overexertion, strain	70	7.6
Pressure release	7	0.8
Slips and trips (at same height)	195	21.3
Struck by (not dropped object)	138	15.1
Water related, drowning	3	0.3
Unspecified - Other	124	13.5
OVERALL	916	

Of the 916 reported lost work day cases (LWDC) resulting in at least one day off work, 713 incidents (78%) were contractor-related and 203 (22%) were company-related (726 and 220 respectively for 2024).

The cause was provided for all LWDC reported, although 14% of the cases were categorized as 'Other'.

Figure 23 shows the percentage of LWDCs within each of the reporting categories for 2025.

Figure 23:



- Slips and trips (at same height) accounted for 195 cases, 21.3% of LWDCs where the cause was given. 2024 results showed 206 cases accounting for 21.8%.
- Caught in, under or between (excl. dropped objects) accounted for 154 cases, 16.8% of the total. 2024 results showed 189 cases accounting for 20.0%.
- Struck by (not dropped object) accounted for 138 cases, 15.1% of the total. 2024 results showed 148 cases accounting for 15.6%.

Results were very similar to previous years.

Table 10: Lost work day cases by cause - company & contractor (2025)

Cause	Company	Contractor
Assault or violent act	0	3
Caught in, under or between (excl. dropped objects)	33	121
Cut, puncture, scrape	4	33
Dropped objects	8	21
Explosion, fire or burns	5	51
Exposure electrical	4	4
Exposure noise, chemical, biological, vibration, extreme temperature	13	23
Falls from height	13	43
Overexertion, strain	22	48
Pressure release	1	6
Slips and trips (at same height)	50	145
Struck by (not dropped object)	26	112
Water related, drowning	1	2
Unspecified - Other	23	101
OVERALL	203	713

Figure 24:

Percentage of lost work day cases by cause - company (2025)




Figure 25:

Percentage of lost work day cases by cause - contractor (2025)




Table 11: Lost work day cases by cause - onshore & offshore (2025)

Cause	Onshore	Offshore
Assault or violent act	3	0
Caught in, under or between (excl. dropped objects)	80	74
Cut, puncture, scrape	20	17
Dropped objects	23	6
Explosion, fire or burns	26	30
Exposure electrical	6	2
Exposure noise, chemical, biological, vibration, extreme temperature	19	17
Falls from height	30	26
Overexertion, strain	36	34
Pressure release	6	1
Slips and trips (at same height)	114	81
Struck by (not dropped object)	78	60
Water related, drowning	0	3
Unspecified - Other	54	70
OVERALL	495	421

Of the 916 reported LWDC resulting in at least one day off work, 495 incidents (54%) were related to onshore activity and 421 (46%) were related to offshore activity (513 and 433 respectively for 2024).

Figure 26:





Figure 27:




Lost work day case (LWDC) activities were reported for all of the 916 LWDC reported, although 15% of the cases were categorized as 'Unspecified - Other'.

Table 12: Lost work day cases by activity (2025)

Activity	Number	% of total
Construction, commissioning, decommissioning	124	13.5
Diving (incl. decompression), subsea, ROV	4	0.4
Drilling, workover, well operations	144	15.7
Excavation, trenching, ground disturbance	8	0.9
Lifting, crane, rigging, deck operations	77	8.4
Maintenance, inspection, testing	173	18.9
Office, warehouse, accommodation, catering	62	6.8
Production operations	150	16.4
Seismic/survey operations	2	0.2
Transport - Land	22	2.4
Transport - Water, incl. marine activity	13	1.4
Unspecified - other	137	15.0
OVERALL	916	

Figure 28:

Percentage of lost work day cases by activity (2025)



Note that Excavation, trenching, ground disturbance was added as an activity in 2019.

Table 13: Lost work day cases by activity - company & contractor (2025)

Activity	Company	Contractor
Construction, commissioning, decommissioning	5	119
Diving (incl. decompression), subsea, ROV	0	4
Drilling, workover, well operations	19	125
Excavation, trenching, ground disturbance	2	6
Lifting, crane, rigging, deck operations	12	65
Maintenance, inspection, testing	53	120
Office, warehouse, accommodation, catering	16	46
Production operations	54	96
Seismic/survey operations	0	2
Transport - Land	9	13
Transport - Water, incl. marine activity	0	13
Unspecified - other	33	104
OVERALL	203	713

Figure 29:

Percentage of lost work day cases by activity - company (2025)




Figure 30:

Percentage of lost work day cases by activity - contractor (2025)




Table 14: Lost work day cases by activity - onshore & offshore (2025)

Activity	Onshore	Offshore
Construction, commissioning, decommissioning	73	51
Diving (incl. decompression), subsea, ROV	0	4
Drilling, workover, well operations	98	46
Excavation, trenching, ground disturbance	8	0
Lifting, crane, rigging, deck operations	34	43
Maintenance, inspection, testing	74	99
Office, warehouse, accommodation, catering	32	30
Production operations	82	68
Seismic/survey operations	1	1
Transport - Land	22	0
Transport - Water, incl. marine activity	1	12
Unspecified - other	70	67
OVERALL	495	421

Figure 31:

Percentage of lost work day cases by activity - onshore (2025)





Figure 32:

Percentage of lost work day cases by activity - offshore (2025)



2.8 Severity of LWDC

For calculations of lost work day case (LWDC) severity:

- Submissions without information on days off work were filtered out, leaving a database of 2,853 million hours, 74% of the total database.
- In 2024, this database was 3,507 million hours, 84% of the total database.

IOGP Member Companies reported a total of 29,703 days lost (LWDC days) through injuries.

- The number of days lost was reported for 703 of the 916 lost work day cases reported.
- The offshore LWDC severity is 2% lower than onshore.
- The LWDC severity for contractors is 30% lower than for company employees.

Table 15: Severity of lost work day cases (2025 compared with 2020-2024)

	Severity of LWDC (average days lost per LWDC)			2025 relative to 2020-2024	2025 relative to 2024
	2020-2024	2024	2025		
OVERALL	46.4	45.3	42.3	9% lower	7% lower
Company	45.6	50.3	55.0	21% higher	9% higher
Contractor	46.6	43.6	38.3	18% lower	12% lower
Onshore	46.7	47.5	42.7	9% lower	10% lower
Offshore	45.9	42.3	41.7	9% lower	1% lower

Figure 33:






Figure 34:



The figure below shows the average number of days lost per LWDC in 2025 compared with the average for the previous five-year period. A 9% decrease is shown in overall LWDC severity when compared with the previous five-year period.

Figure 35:



2.9 Severity of RWDC

For calculations of restricted work day case (RWDC) severity:

- Submissions without information on days assigned to restricted activities were filtered out, leaving a database of 2,203 million hours (57% of the total database), and 475 restricted work day cases.
- In 2024, this database was 3,085 million hours, 74% of the total database.

In total, 11,585 days were restricted (RWDC days) as a result of restricted work day cases, in the sense that normal duties could not be performed.

See [Appendix A](#) and [Appendix C](#).

Table 16: Severity of RWDC (2025 compared with 2020-2024)

	Severity of RWDC (average days restricted per RWDC)			2025 relative to 2020-2024	2025 relative to 2024
	2020-2024	2024	2025		
OVERALL	28.7	33.6	24.4	15% lower	27% lower
Company	31.2	30.0	22.8	27% lower	24% lower
Contractor	28.3	34.2	24.7	13% lower	28% lower
Onshore	29.3	33.1	22.4	24% lower	32% lower
Offshore	27.5	34.7	28.5	4% higher	18% lower

Figure 36:






Figure 37:



The figure below shows the average number of days restricted per RWDC in 2025 compared with the average for the previous five-year period. The overall average shows a reduction of 15% compared with the average for the previous five-year period.

Figure 38:



2.10 Incident triangles

In this section, the relative numbers of types of occupational injury are shown in the form of ‘incident triangles’. The ratios have been corrected to account for the absence, in some data submissions, of medical treatment cases.

Table 17: Ratio of lost time injuries and recordable injuries to fatalities (2016-2025)

Year	Ratio of lost time injuries to fatalities	Ratio of total recordable injuries to fatalities
2025	19:1	52:1
2024	31:1	96:1
2023	29:1	103:1
2022	22:1	69:1
2021	30:1	101:1
2020	40:1	122:1
2019	29:1	110:1
2018	26:1	98:1
2017	24:1	85:1
2016	16:1	60:1

Definitions

Lost time injuries (LTI):

Lost work day cases and fatalities.

Total recordable injuries (TRI):

Fatalities, lost work day cases, restricted work day cases, and medical treatment cases where medical treatment cases are reported for the data set.

Ratio of lost time injuries to fatalities:

The number of lost time injuries divided by the total number of fatalities (lost time injuries/fatalities).

Ratio of total recordable injuries to fatalities:

The number of recordable injuries divided by the total number of fatalities (recordable injuries/fatalities).

Figure 39:





Figure 40:



The varying ratio of fatalities to lost time injuries to recordable injuries for 2024-2025 challenges the traditional notion of recordable injuries and lost time injuries overall as a precursor to fatalities, as shown in the incident triangles.

Table 18: Ratio of fatalities to lost time injuries by cause (2025)

Cause	LTIs (fatalities + LWDCs)	Fatalities	Ratio (LTI:Fatality)
Assault or violent act	7	4	2:1
Water related, drowning	7	4	2:1
Dropped objects	37	8	5:1
Exposure electrical	10	2	5:1
Explosion, fire or burns	62	6	10:1
Falls from height	61	5	12:1
Caught in, under or between (excl. dropped objects)	163	9	18:1
Struck by (not dropped object)	146	8	18:1
Exposure noise, chemical, biological, vibration, extreme temperature	37	1	37:1
Unspecified - Other	126	2	63:1
Slips and trips (at same height)	195	0	n/a
Overexertion, strain	70	0	n/a
Cut, puncture, scrape	37	0	n/a
Pressure release	7	0	n/a

Table 19: Ratio of fatalities to lost time injuries by activity (2025)

Activity	LTIs (fatalities + LWDCs)	Fatalities	Ratio (LTI:Fatality)
Transport - Land	32	10	3:1
Maintenance, inspection, testing	187	14	13:1
Lifting, crane, rigging, deck operations	83	6	14:1
Drilling, workover, well operations	153	9	17:1
Production operations	155	5	31:1
Construction, commissioning, decommissioning	128	4	32:1
Unspecified - other	138	1	138:1
Office, warehouse, accommodation, catering	62	0	n/a
Transport - Water, incl. marine activity	13	0	n/a
Excavation, trenching, ground disturbance	8	0	n/a
Diving (incl. decompression), subsea, ROV	4	0	n/a
Seismic/survey operations	2	0	n/a

2.11 Causal factors

The allocation of causal factors to fatal incidents and high potential events was requested as part of the data submission. IOGP first began recording causal factors in 2010. Users now have 15 years worth of data on this topic to use for comparisons.

To standardize the response, an IOGP glossary and list of causal factors was provided to Member Companies as part of the IOGP user guide. The causal factors list is divided into two sections:

- People (Acts) classifications usually involve either the actions of a person or actions which were required but not carried out or were incorrectly performed. There are four major categories of actions, with an additional level of detail under each of the major categories.
- Process (Conditions) classifications usually involve some type of physical hazard or organizational aspect out of the control of the individual. There are five major classification categories, with an additional level of detail under each of the major categories.

Definitions

High potential event

An event which could have, under slightly different circumstances, realistically resulted in a fatal incident.

2.12 Fatal incident causal factors

Causal factors are divided into two separate groups, People (Acts) and Process (Conditions), see [Report 2025su Safety data reporting user guide – 2025 data](#) and [Glossary](#) for details.

- 37 of the 40 fatal incidents reported were assigned causal factors (17 of 21 in 2024).
- 169 causal factors were assigned for the 37 fatal incidents (46 in 2024).
- Between 1 and 10 causal factors were assigned per incident (between 1 and 12 in 2024).

Table 20: Causal factors assigned to fatal incidents (2024 & 2025)

Causal factor group	2024	2025
PEOPLE (ACTS)	22	79
PROCESS (CONDITIONS)	24	90

The causal factors assigned to fatal incidents are shown in Table 21. The highlighted content indicates the top ten causal factors assigned to fatal incidents in 2025 compared with the previous 9 years. 3 of the causal factors were in the top ten for the 10 years shown, and for each of the 10 years for which data were reported.

Additional information on the fatal incidents reported by region can be found at <https://data.iogp.org/Safety/FatalIncidents>. The information provided includes a narrative description of the incident, the corrective actions and recommendations, and the causal factors assigned by the reporting company.

Table 21: Causal factors assigned to fatal incidents (2016 - 2025)

Causal factor	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	Total
PEOPLE (ACTS) : Following Procedures : Improper position (in the line of fire)	11	7	13	7	2	3	17	4	5	25	94
PROCESS (CONDITIONS) : Organizational : Inadequate hazard identification or risk assessment	10	10	15	9	1	5	6	3	3	25	87
PROCESS (CONDITIONS) : Organizational : Inadequate supervision	9	12	17	7	4	5	5	1	4	8	72
PEOPLE (ACTS) : Inattention/Lack of Awareness : Improper decision making or lack of judgment	13	9	14	9	2	6	4	0	4	8	69
PROCESS (CONDITIONS) : Organizational : Inadequate training/competence	6	4	11	3	3	3	4	2	1	7	44
PROCESS (CONDITIONS) : Organizational : Inadequate work standards/procedures	4	4	3	3	3	7	3	0	4	11	42
PEOPLE (ACTS) : Use of Protective Methods : Failure to warn of hazard	5	5	4	4	0	2	3	1	2	6	32
PEOPLE (ACTS) : Following Procedures : Deviation unintentional (by individual or group)	2	6	5	5	2	2	4	1	1	4	32
PROCESS (CONDITIONS) : Tools, Equipment, Materials and Products : Inadequate maintenance/inspection/testing	4	2	6	0	1	1	4	1	2	10	31
PROCESS (CONDITIONS) : Protective Systems : Inadequate/defective guards or protective barriers	2	8	4	4	0	3	4	0	1	3	29
PROCESS (CONDITIONS) : Organizational : Inadequate communication	3	1	5	3	3	2	5	0	1	4	27
PROCESS (CONDITIONS) : Tools, Equipment, Materials and Products : Inadequate design/specification/management of change	1	2	3	1	1	1	6	1	2	7	25
PEOPLE (ACTS) : Use of Tools, Equipment, Materials and Products : Servicing of energized equipment/inadequate energy isolation	2	3	2	2	2	1	5	1	1	4	23
PROCESS (CONDITIONS) : Tools, Equipment, Materials and Products : Inadequate/defective tools/equipment/materials/products	3	5	2	1	1	2	1	0	2	5	22
PEOPLE (ACTS) : Use of Protective Methods : Equipment or materials not secured	2	1	4	2	0	2	1	0	0	9	21
PEOPLE (ACTS) : Following Procedures : Improper lifting or loading	2	0	6	2	0	1	3	1	0	6	21
PEOPLE (ACTS) : Use of Tools, Equipment, Materials and Products : Improper use/position of tools/equipment/materials/products	3	4	4	1	1	2	1	0	3	2	21
PEOPLE (ACTS) : Inattention/Lack of Awareness : Lack of attention/distracted by other concerns/stress	6	4	1	4	1	0	2	0	1	0	19
PEOPLE (ACTS) : Following Procedures : Deviation intentional (by individual or group)	2	2	5	1	0	0	1	1	2	1	15
PEOPLE (ACTS) : Use of Protective Methods : Inadequate use of safety systems	1	1	4	1	1	0	0	0	1	5	14
PEOPLE (ACTS) : Following Procedures : Work or motion at improper speed	2	4	1	1	0	1	2	1	0	2	14
PROCESS (CONDITIONS) : Organizational : Poor leadership/organizational culture	0	6	3	0	1	1	0	0	1	1	13
PEOPLE (ACTS) : Use of Protective Methods : Personal Protective Equipment not used or used improperly	1	2	1	2	0	2	1	1	0	3	13
PROCESS (CONDITIONS) : Protective Systems : Inadequate/defective warning systems/safety devices	2	1	2	1	0	1	1	1	1	1	11
PROCESS (CONDITIONS) : Organizational : Failure to report/learn from events	2	0	2	3	0	1	0	1	0	0	9
PROCESS (CONDITIONS) : Work Place Hazards : Hazardous atmosphere (explosive/toxic/asphyxiant)	1	1	0	0	0	0	1	1	2	3	9
PROCESS (CONDITIONS) : Work Place Hazards : Congestion, clutter or restricted motion	1	1	2	0	0	1	3	0	0	1	9
PROCESS (CONDITIONS) : Work Place Hazards : Inadequate surfaces, floors, walkways or roads	3	0	0	0	1	0	0	1	0	3	8
PEOPLE (ACTS) : Inattention/Lack of Awareness : Fatigue	1	2	0	1	0	1	1	0	1	1	8
PEOPLE (ACTS) : Use of Protective Methods : Disabled or removed guards, warning systems or safety devices	1	0	2	0	0	1	0	0	1	2	7
PROCESS (CONDITIONS) : Protective Systems : Inadequate/defective Personal Protective Equipment	0	1	0	2	0	1	0	0	0	1	5
PEOPLE (ACTS) : Inattention/Lack of Awareness : Acts of violence	0	2	0	0	0	1	0	0	0	1	4
PROCESS (CONDITIONS) : Work Place Hazards : Storms or acts of nature	1	1	1	0	0	0	0	0	0	0	3
PEOPLE (ACTS) : Following Procedures : Overexertion or improper position/posture for task	1	1	1	0	0	0	0	0	0	0	3
PEOPLE (ACTS) : Inattention/Lack of Awareness : Use of drugs or alcohol	0	1	0	0	0	1	0	0	0	0	2
PROCESS (CONDITIONS) : Protective Systems : Inadequate security provisions or systems	0	1	1	0	0	0	0	0	0	0	2

Causal factors are listed in order of frequency for 2025. The top 10 causal factors assigned to fatal incidents for each year are highlighted.

2025: 2 causal factors were equal 10th with 6 assigned incidents (11 factors are highlighted)

2024: 6 causal factors were equal 7th with 2 assigned incidents (12 factors are highlighted)

2023: 14 causal factors were equal 4th with 1 assigned incident (17 factors are highlighted)

2022: 5 causal factors were equal 7th with 4 assigned incidents (11 factors are highlighted)

2021: 7 causal factors were equal 8th with 2 assigned incidents (14 factors are highlighted)

2020: 9 causal factors were equal 9th with 1 assigned incident (17 factors are highlighted)

2019: 4 causal factors were equal 9th with 3 assigned incidents (12 factors are highlighted)

2017: 5 causal factors were equal 10th with 4 assigned incidents (14 factors are highlighted)

2016: 4 causal factors were equal 10th with 3 assigned incidents (13 factors are highlighted)

2.13 High potential event causal factors

High potential events are defined as 'an event which could have, under slightly different circumstances, realistically resulted in a fatal incident'. Participating companies are invited to submit a small number of high potential event reports and to select those with the greatest learning value. The data reported here therefore do not represent the total number of events for the participating companies, so care should be taken in interpreting the data presented in this section.

- 131 of the 133 high potential events reported were assigned causal factors (156 of 159 in 2024).
- 645 causal factors were assigned for the 131 high potential events (602 in 2024).
- Between 1 and 11 causal factors were assigned per event (between 1 and 12 in 2024).

Table 22: Causal factors assigned to high potential events (2024 & 2025)

Causal factor group	2024	2025
PEOPLE (ACTS)	236	301
PROCESS (CONDITIONS)	366	344

The causal factors assigned to high potential events are shown in Table 23. The highlighted content indicates the top ten causal factors assigned to high potential events in 2025 compared with the previous 9 years. 4 of the causal factors were in the top ten for the 10 years shown.

Additional information on the high potential events reported by region can be found at <https://data.iogp.org/Safety/HighPotentialEvents>. The information provided includes a narrative description of the incident, the corrective actions and recommendations, and the causal factors assigned by the reporting company.

Table 23: Causal factors assigned to high potential events (2016 - 2025)

Causal factor	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	Total
PROCESS (CONDITIONS) : Organizational : Inadequate hazard identification or risk assessment	116	54	48	60	29	35	43	44	72	95	596
PROCESS (CONDITIONS) : Organizational : Inadequate work standards/procedures	80	49	36	38	26	31	37	41	61	41	440
PROCESS (CONDITIONS) : Tools, Equipment, Materials and Products : Inadequate design/specification/management of change	68	40	33	24	14	38	24	26	29	30	326
PEOPLE (ACTS) : Inattention/Lack of Awareness : Improper decision making or lack of judgment	81	36	29	38	14	20	17	25	16	24	300
PROCESS (CONDITIONS) : Tools, Equipment, Materials and Products : Inadequate maintenance/inspection/testing	54	28	27	23	25	31	22	23	34	31	298
PROCESS (CONDITIONS) : Organizational : Inadequate training/competence	47	30	33	29	23	18	14	29	30	33	286
PEOPLE (ACTS) : Following Procedures : Improper position (in the line of fire)	35	8	14	10	7	6	6	15	80	102	283
PROCESS (CONDITIONS) : Organizational : Inadequate supervision	44	26	28	29	16	17	21	16	34	19	250
PEOPLE (ACTS) : Use of Tools, Equipment, Materials and Products : Improper use/position of tools/equipment/materials/products	58	23	20	22	18	19	15	10	29	20	234
PROCESS (CONDITIONS) : Tools, Equipment, Materials and Products : Inadequate/defective tools/equipment/materials/products	57	21	20	29	15	23	11	16	19	12	223
PROCESS (CONDITIONS) : Organizational : Inadequate communication	39	22	15	30	18	15	17	17	23	22	218
PEOPLE (ACTS) : Following Procedures : Deviation unintentional (by individual or group)	58	18	16	21	15	11	14	23	23	14	213
PEOPLE (ACTS) : Use of Protective Methods : Equipment or materials not secured	62	13	10	13	11	5	11	12	10	36	183
PROCESS (CONDITIONS) : Protective Systems : Inadequate/defective guards or protective barriers	51	14	16	22	10	12	9	6	23	15	178
PEOPLE (ACTS) : Inattention/Lack of Awareness : Lack of attention/distracted by other concerns/stress	48	21	16	8	7	9	9	10	7	12	147
PEOPLE (ACTS) : Use of Protective Methods : Failure to warn of hazard	40	11	12	7	10	12	11	9	16	18	146
PEOPLE (ACTS) : Following Procedures : Improper lifting or loading	34	3	5	9	8	11	8	8	17	22	125
PEOPLE (ACTS) : Use of Protective Methods : Inadequate use of safety systems	19	7	15	6	8	5	10	5	6	11	92
PEOPLE (ACTS) : Use of Tools, Equipment, Materials and Products : Servicing of energized equipment/inadequate energy isolation	19	6	10	7	5	5	6	7	8	16	89
PROCESS (CONDITIONS) : Protective Systems : Inadequate/defective warning systems/safety devices	17	7	10	13	7	7	6	10	7	4	88
PEOPLE (ACTS) : Following Procedures : Deviation intentional (by individual or group)	24	9	4	12	2	7	2	8	12	6	86
PROCESS (CONDITIONS) : Organizational : Poor leadership/organizational culture	15	14	13	5	3	3	4	3	12	8	80
PROCESS (CONDITIONS) : Organizational : Failure to report/learn from events	13	4	5	6	4	5	3	7	4	6	57
PROCESS (CONDITIONS) : Work Place Hazards : Storms or acts of nature	17	1	3	1	2	7	2	7	5	8	53
PROCESS (CONDITIONS) : Work Place Hazards : Hazardous atmosphere (explosive/toxic/asphyxiant)	17	1	6	4	3	1	2	4	4	6	48
PEOPLE (ACTS) : Use of Protective Methods : Personal Protective Equipment not used or used improperly	9	3	4	5	2	4	3	5	3	6	44
PROCESS (CONDITIONS) : Work Place Hazards : Inadequate surfaces, floors, walkways or roads	15	4	3	0	0	6	1	0	5	9	43
PROCESS (CONDITIONS) : Work Place Hazards : Congestion, clutter or restricted motion	11	5	4	3	1	1	2	0	3	5	35
PEOPLE (ACTS) : Use of Protective Methods : Disabled or removed guards, warning systems or safety devices	9	1	1	5	1	5	3	5	2	3	35
PEOPLE (ACTS) : Following Procedures : Work or motion at improper speed	4	3	1	1	2	2	2	3	4	8	30
PEOPLE (ACTS) : Inattention/Lack of Awareness : Fatigue	5	2	3	3	1	4	2	3	2	3	28
PROCESS (CONDITIONS) : Protective Systems : Inadequate security provisions or systems	4	1	4	0	2	1	4	0	0	0	16
PROCESS (CONDITIONS) : Protective Systems : Inadequate/defective Personal Protective Equipment	2	3	1	3	0	1	1	1	1	0	13
PEOPLE (ACTS) : Following Procedures : Overexertion or improper position/posture for task	1	2	2	1	2	2	1	0	1	0	12
PEOPLE (ACTS) : Inattention/Lack of Awareness : Acts of violence	2	0	0	0	0	0	0	0	0	0	2
PEOPLE (ACTS) : Inattention/Lack of Awareness : Use of drugs or alcohol	1	0	0	0	0	0	0	0	0	0	1

Causal factors are listed in order of frequency for 2025. The top 10 causal factors assigned to high potential events for each year are highlighted.

2024: 3 causal factors were equal 9th with 23 assigned events (11 factors are highlighted)

2020: 2 causal factors were equal 10th with 14 assigned events (11 factors are highlighted)

2019: 2 causal factors were equal 10th with 22 assigned events (11 factors are highlighted)

2018: 3 causal factors were equal 10th with 16 assigned events (12 factors are highlighted)

2017: 2 causal factors were equal 10th with 21 assigned events (11 factors are highlighted)

2.14 Life-Saving Rules

In 2010, IOGP released IOGP Report 459 - *Life-Saving Rules*, intended for use by the oil and gas industry to mitigate risk and reduce fatalities. Each IOGP Life-Saving Rule consisted of a simple icon and descriptive text, providing clear, simple, and consistent communication about risks in the workplace.

These Rules were developed by using the fatal incident and high potential event data from the 1991 to 2010 Safety Performance Indicators Reports to identify the events and activities that are the highest risk and therefore provide clear instructions on how to avoid them.

In 2018, IOGP re-examined the applicability of the 2010 Rules against the most recent fatality data. With the 2018 revision of Report 459, IOGP launched a simplified set of Life-Saving Rules (Figure 41) to provide workers in the industry with the actions they can take to protect themselves and their colleagues from fatalities. With a reduced number of rules (9 reduced from 18), but still covering a similar scope, IOGP aims to improve the level of industry-wide adoption across the global oil and gas industry.

Figure 41: Life-Saving Rules (from IOGP Report 459)

Bypassing Safety Controls Obtain authorisation before overriding or disabling safety controls  • I understand and use safety-critical equipment and procedures which apply to my task • I obtain authorisation before: – disabling or overriding safety equipment – deviating from procedures – crossing a barrier	Confined Space Obtain authorisation before entering a confined space  • I confirm energy sources are isolated • I confirm the atmosphere has been tested and is monitored • I check and use my breathing apparatus when required • I confirm there is an attendant standing by • I confirm a rescue plan is in place • I obtain authorisation to enter	Driving Follow safe driving rules  • I always wear a seatbelt • I do not exceed the speed limit, and reduce my speed for road conditions • I do not use phones or operate devices while driving • I am fit, rested and fully alert while driving • I follow journey management requirements
Energy Isolation Verify isolation and zero energy before work begins  • I have identified all energy sources • I confirm that hazardous energy sources have been isolated, locked, and tagged • I have checked there is zero energy and tested for residual or stored energy	Hot Work Control flammables and ignition sources  • I identify and control ignition sources • Before starting any hot work: – I confirm flammable material has been removed or isolated – I obtain authorisation • Before starting hot work in a hazardous area I confirm: – a gas test has been completed – gas will be monitored continually	Line of Fire Keep yourself and others out of the line of fire  • I position myself to avoid: – moving objects – vehicles – pressure releases – dropped objects • I establish and obey barriers and exclusion zones • I take action to secure loose objects and report potential dropped objects
Safe Mechanical Lifting Plan lifting operations and control the area  • I confirm that the equipment and load have been inspected and are fit for purpose • I only operate equipment that I am qualified to use • I establish and obey barriers and exclusion zones • I never walk under a suspended load	Work Authorisation Work with a valid permit when required  • I have confirmed if a permit is required • I am authorised to perform the work • I understand the permit • I have confirmed that hazards are controlled and it is safe to start • I stop and reassess if conditions change	Working at Height Protect yourself against a fall when working at height  • I inspect my fall protection equipment before use • I secure tools and work materials to prevent dropped objects • I tie off 100% to approved anchor points while outside a protected area

In 2021, IOGP released IOGP Report 459-1 - *Life-Saving Rules – Start Work Checks*, a set of standardized and simplified checklists of safeguards that workers complete at the job location immediately before work commences. The Start Work Checks are supplemental to the Life-Saving Rules (Report 459).

Assessment of the applicability of the IOGP Life-Saving Rules to fatal incident descriptions for 2025 data has shown that at least 85% of the fatal incidents reported are covered by the IOGP Life-Saving Rules and may have been prevented by the adoption of this system.

Incidents where there was no applicable rule have been excluded from figure 42.

Figure 42:

Percentage of Life-Saving Rules allocated to fatal incidents where a rule was allocated (2025)





Table 24: IOGP Life-Saving Rules allocated to fatal incidents (2025)

Life-Saving Rule	Fatal incidents				
	2021	2022	2023	2024	2025
Bypassing safety controls	0	0	2	1	2
Confined space	0	0	0	2	1
Driving	1	2	3	4	3
Energy isolation	1	4	1	1	4
Hot work	0	3	0	1	2
Line of fire	5	12	2	3	12
Safe mechanical lifting	3	2	2	1	6
Work authorization	0	1	1	3	1
Working at height	4	1	2	2	3
Other issue – no applicable rule	0	4	4	3	5
Unspecified	1	0	0	0	1

Figure 43:



Assessment of the applicability of the IOGP Life-Saving Rules to lost work day cases (LWDC) for 2025 data has shown that at least 48% of the LWDC reported are covered by the IOGP Life-Saving Rules and may have been prevented by the adoption of this system.

Incidents where there was no applicable rule have been excluded from figure 44.

Figure 44:

Percentage of Life-Saving Rules allocated to lost work day cases where a rule was allocated (2025)





Table 25: IOGP Life-Saving Rules allocated to Lost work day cases (2025)

Life-Saving Rule	Lost work day cases				
	2021	2022	2023	2024	2025
Bypassing safety controls	5	5	23	25	13
Confined space	2	7	2	7	6
Driving	7	13	16	33	20
Energy isolation	20	20	22	22	33
Hot work	7	6	4	5	7
Line of fire	109	176	210	215	255
Safe mechanical lifting	42	23	47	46	43
Work authorization	7	17	13	28	24
Working at height	44	37	30	41	42
Other issue – no applicable rule	200	180	140	186	176
Unspecified	137	198	241	338	297

Figure 45:



See [Appendix B - Section 2](#) for data tables.

3. Results by region

In this section, the safety performance of the contributing IOGP Member Companies is presented for regions and individual countries within those regions.


Indicators used to measure contributing IOGP Member Companies' safety performance are:

- number of fatalities
- fatal accident rate (FAR)
- total recordable injury rate (TRIR)
- lost time injury rate (LTIR)
- FAR, TRIR, and LTIR five-year rolling averages
- severity of lost work day cases (LWDC)
- individual country performance
- incident triangles by region
- fatalities by incident category and activity

Third party fatalities are not included in this analysis.

Maps showing the division of countries into regions, and the work hours and number of participating companies by country, are provided in [Appendix D](#).

Countries and companies that are subject to international sanctions (Russia and Iran) are not featured in this Report for 2022-2025 data.



Definitions

Fatal accident rate (FAR):

The number of company/contractor fatalities per 100 million hours worked.

Fatal incidents per 100 million work hours (FIR):

The number of incidents that result in one or more fatalities per 100 million hours worked.

Total recordable injury rate (TRIR)

The number of recordable injuries (fatalities + lost work day cases + restricted work day cases + medical treatment cases (MTC)) per million hours worked. Note when MTC or RWDC are not reported by a company for a country the associated work hours, fatalities, lost work day cases, restricted work day cases and medical treatment cases are excluded from TRIR calculations.

Lost time injury rate (LTIR)

The number of lost time injuries (fatalities + lost work day cases) per million hours worked.

Five-year rolling average

The five-year rolling average is calculated by summing the total number of incidents for the five previous years and dividing by the sum of the work hours for these years. The number series involved in the calculation is frame shifted along by one each year, e.g., 2025 will be calculated from 2021-2025 data. For example, the five-year rolling average FAR for 2025 is calculated by:

$$\frac{(\text{Number of fatalities in 2021} + \text{2022} + \text{2023} + \text{2024} + \text{2025})}{(\text{Total work hours in 2021} + \text{2022} + \text{2023} + \text{2024} + \text{2025}) / 100,000,000}$$

Lost work day case (LWDC)

An incident resulting in at least one day off work. Fatal incidents are not included.

LWDC Severity

The average number of days lost (where reported) for each lost work day case.

3.1 Fatalities

Table 26 shows the number of fatalities, fatal incidents, and fatal accident rate in each of the seven regions into which the data are partitioned.

Table 26: Fatalities, fatal incidents, and fatal accident rate by region (2024 - 2025)

Region	Fatalities		Fatal accident rate (FAR)		Fatal incidents	
	2024	2025	2024	2025	2024	2025
Africa	8	8	1.67	2.03	3	5
Asia/Australasia	3	18	0.34	2.29	2	15
Europe	1	1	0.43	0.47	1	1
Middle East	9	8	0.77	0.65	6	7
North America	7	5	0.93	0.78	5	5
Russia & Central Asia	2	8	0.88	3.47	2	5
South & Central America	2	4	0.48	1.15	2	2
OVERALL	32	52	0.77	1.35	21	40


3.2 Fatal accident rate

Further fatal accident rate (FAR) analysis is presented in [Section 3.5](#), where five-year rolling averages of FAR are presented for each of the regions.

Table 27: Fatal accident rate by region (2021 - 2025)

Region	Fatal accident rate (FAR)				
	2021	2022	2023	2024	2025
Africa	2.16	0.54	1.29	1.67	2.03
Asia/Australasia	0.00	1.44	1.94	0.34	2.29
Europe	0.87	0.00	0.00	0.43	0.47
Middle East	0.60	2.17	0.40	0.77	0.65
North America	0.38	1.21	0.78	0.93	0.78
Russia & Central Asia	0.60	0.94	1.29	0.88	3.47
South & Central America	1.14	1.93	0.00	0.48	1.15
OVERALL	0.75	1.28	0.82	0.77	1.35

Figure 46:




3.3 Total recordable injury rate

Submissions without information on medical treatment cases were filtered out, leaving a database of 3,535 million hours (92% of the database). See [Appendix A – Database dimensions](#).

Table 28: Total recordable injury rate by region (2021 - 2025)

Region	Total recordable injury rate (TRIR)				
	2021	2022	2023	2024	2025
Africa	0.39	0.37	0.36	0.42	0.53
Asia/Australasia	0.69	0.77	0.66	0.53	0.59
Europe	1.93	1.82	1.67	2.06	2.22
Middle East	0.30	0.30	0.40	0.44	0.37
North America	1.40	1.61	1.70	1.62	1.41
Russia & Central Asia	0.46	0.60	0.52	0.67	0.96
South & Central America	1.14	1.45	1.62	1.43	1.05
OVERALL	0.77	0.90	0.84	0.81	0.76

Figure 47:




3.4 Lost time injury rate

Further analysis of the lost time injuries is presented in [Section 3.5](#), where five-year rolling averages of lost time injury rate (LTIR) are presented for each of the regions.

Table 29: Lost time injury rate by region (2021 - 2025)

Region	Lost time injury rate (LTIR)				
	2021	2022	2023	2024	2025
Africa	38.0	40.1	21.7	43% lower	46% lower
Asia/Australasia	41.9	37.4	50.3	20% higher	35% higher
Europe	40.9	43.9	49.0	20% higher	12% higher
Middle East	29.4	22.9	26.5	10% lower	16% higher
North America	55.3	59.7	56.7	3% higher	5% lower
Russia & Central Asia	64.4	52.8	64.2	0.3% lower	22% higher
South & Central America	51.7	54.6	33.8	35% lower	38% lower
OVERALL	46.4	45.3	42.3	9% lower	7% lower

Figure 48:



3.5 FAR, TRIR, and LTIR five-year rolling averages

In order to smooth out variability in the annual values for the regional FAR, TRIR, and LTIR, five-year rolling averages are computed, which should provide a more reliable indicator of performance trends.

The figures show FAR, TRIR, and LTIR 5-year rolling averages for each of the regions and includes the ‘overall’ curve.

Figure 49:




Figure 50:





Figure 51:



3.6 Severity of LWDC

The number of days lost was reported for 77% of lost work day cases (LWDC).

The severity of LWDCs is the highest in the Russia & Central Asia region [64 days lost per LWDC in 2025]. This is a 1% decrease compared with the average for the previous five-year period.

Data table A2 in [Appendix A](#) provides further information on the proportion of the database that can be used for LWDC severity. 93% of the data submitted for Africa and 93% of the data submitted for Russia & Central Asia were usable for this metric, in comparison with only 51% of equivalent data for Asia/Australasia, and 56% for North America. At least 57% of the data submitted for all other regions were usable for this metric.

Table 30: Severity of lost work day cases by region (2025 compared with 2020-2024)

Region	Severity of LWDC (average days lost per LWDC)			2025 relative to 2020-2024	2025 relative to 2024
	2020-2024	2024	2025		
Africa	38.0	40.1	21.7	43% lower	46% lower
Asia/Australasia	41.9	37.4	50.3	20% higher	35% higher
Europe	40.9	43.9	49.0	20% higher	12% higher
Middle East	29.4	22.9	26.5	10% lower	16% higher
North America	55.3	59.7	56.7	3% higher	5% lower
Russia & Central Asia	64.4	52.8	64.2	0.3% lower	22% higher
South & Central America	51.7	54.6	33.8	35% lower	38% lower
OVERALL	46.4	45.3	42.3	9% lower	7% lower

Figure 52:



3.7 Individual country performance

The safety performance reported by participating IOGP Member Companies in individual countries is presented in terms of the lost time injury rate of companies jointly with contractors. To preserve the anonymity of companies, performance is only published for those countries for which at least 2 companies have reported statistics. Countries with less than 50,000 reported work hours are excluded, since results for such small populations of hours would be unrepresentative. Overall averages and regional averages include data from all countries regardless of work hours or number of contributing companies.

26 of the 87 countries for which data have been reported are excluded by these constraints.

TRIR calculations exclude data where medical treatment cases are not reported. The chart of relative TRIR performance therefore compares the 2025 performance with that of 2024 and 2023 for all of the 61 countries.

The majority of countries in Africa, Asia/Australasia, and the Middle East achieved a TRIR equal to or lower than the overall average TRIR (0.76). The majority of countries in Europe and North America show a TRIR higher than the global average. In Russia & Central Asia and South & Central America, an equal number of countries show a TRIR higher and lower than the global average.

The chart of relative LTIR performance for the 61 countries compares the 2025 performance with that of 2024 and 2023.

The majority of countries in Africa, Asia/Australasia, the Middle East, and North America achieved a LTIR equal to or lower than the overall average LTIR (0.25). The majority of countries in Europe and Russia & Central Asia show a LTIR higher than the global average. In South & Central America, an equal number of countries show a LTIR higher and lower than the global average.

For comparison, the 5-year rolling average FAR is shown for each of the regions. There appears to be little if any correlation between these values and the regional average LTIR and TRIR values.

Figure 53:





Figure 54:



3.8 Incident triangles by region

In this section, the relative numbers of types of occupational injury are shown in the form of 'incident triangles'. The ratios have been corrected to account for the absence, in some data submissions, of medical treatment cases.

Definitions

Lost time injuries (LTI):

Lost work day cases and fatalities.

Total recordable injuries (TRI):

Fatalities, lost work day cases, restricted work day cases, and medical treatment cases where medical treatment cases are reported for the data set.

Ratio of LTI to fatalities:

The number of LTI divided by the total number of fatalities (LTI/fatalities).

Ratio of TRI to fatalities:

The number of TRI divided by the total number of fatalities (Lost time injury rate/fatalities). Note: data are excluded from TRI where medical treatment cases are not reported.

Table 31: Ratio of LTI and TRI to fatalities - Africa (2022-2025)

Year	Ratio of LTI to fatalities	Ratio of TRI to fatalities
2025	9:1	26:1
2024	9:1	95:1
2023	8:1	28:1
2022	21:1	69:1

Figure 55:




Table 32: Ratio of LTI and TRI to fatalities - Asia/Australasia (2022-2025)

Year	Ratio of LTI to fatalities	Ratio of TRI injuries to fatalities
2025	5:1	26:1
2024	34:1	154:1
2023	7:1	34:1
2022	11:1	54:1

Figure 56:




Table 33: Ratio of LTI and TRI to fatalities - Europe (2022-2025)

Year	Ratio of LTI to fatalities	Ratio of TRI injuries to fatalities
2025	220:1	452:1
2024	210:1	466:1
2023	N/A	N/A
2022	N/A	N/A

Figure 57:




Table 34: Ratio of LTI and TRI to fatalities - Middle East (2022-2025)

Year	Ratio of LTI to fatalities	Ratio of TRI to fatalities
2025	18:1	57:1
2024	15:1	57:1
2023	25:1	102:1
2022	4:1	14:1

Figure 58:




Table 35: Ratio of LTI and TRI to fatalities - North America (2022-2025)

Year	Ratio of LTI to fatalities	Ratio of TRI to fatalities
2025	34:1	201:1
2024	31:1	232:1
2023	45:1	218:1
2022	28:1	133:1

Figure 59:





Table 36: Ratio of LTI and TRI to fatalities - Russia & Central Asia (2022-2025)

Year	Ratio of LTI to fatalities	Ratio of TRI to fatalities
2025	10:1	132:1
2024	27:1	77:1
2023	14:1	40:1
2022	17:1	55:1

Figure 60:




Note: data are only included in TRI where medical treatment cases are reported.

Table 37: Ratio of LTI and TRI to fatalities - South America (2022-2025)

Year	Ratio of LTI to fatalities	Ratio of TRI to fatalities
2025	46:1	92:1
2024	96:1	293:1
2023	N/A	N/A
2022	33:1	75:1

Figure 61:



See [Appendix B - Section 3](#) for data tables.

4. Results by function

In this section, safety performance within different functions performed in the E&P industry is presented for 2025. Functions are defined as ‘exploration’, ‘drilling’, ‘production’, ‘construction’, and ‘unspecified’.

See the [Glossary of Terms](#) for definitions.

The percentage of the total work hours reported under each function has been detailed below. See [Appendix B](#) for further data.

Table 38: Percentage of total work hours reported under each function (2021-2025)

Function	Percentage of total work hours				
	2021	2022	2023	2024	2025
Exploration	1.4	1.1	1.3	1.3	2.0
Drilling	12.3	12.7	15.0	17.2	13.7
Production	49.5	49.1	45.6	44.4	45.2
Construction	20.9	17.9	18.4	19.3	19.4
Unspecified	15.9	19.2	19.7	17.7	19.8

Table 38A: Total work hours reported (2021-2025)

Function	Work hours (thousands)				
	2021	2022	2023	2024	2025
OVERALL	2,679,026	2,579,000	3,291,382	4,158,877	3,854,622

Definitions

Fatal accident rate (FAR):

The number of company/contractor fatalities per 100 million hours worked.

Fatal incidents per 100 million work hours (FIR):

The number of incidents that result in one or more fatalities per 100 million hours worked.

Total recordable injury rate (TRIR)

The number of recordable injuries (fatalities + lost work day cases + restricted work day cases + medical treatment cases (MTC)) per million hours worked. Note when MTC or RWDC are not reported by a company for a country the associated work hours, fatalities, lost work day cases, restricted work day cases and medical treatment cases are excluded from TRIR calculations.

Lost time injury rate (LTIR)

The number of lost time injuries (fatalities + lost work day cases) per million hours worked.

Five-year rolling average

The five-year rolling average is calculated by summing the total number of incidents for the five previous years and dividing by the sum of the work hours for these years. The number series involved in the calculation is frame shifted along by one each year, e.g., 2025 will be calculated from 2021-2025 data. For example, the five-year rolling average FAR for 2025 is calculated by:

$$\frac{(\text{Number of fatalities in 2021} + \text{2022} + \text{2023} + \text{2024} + \text{2025})}{(\text{Total work hours in 2021} + \text{2022} + \text{2023} + \text{2024} + \text{2025}) / 100,000,000}$$

Lost work day case (LWDC)

An incident resulting in at least one day off work. Fatal incidents are not included.

LWDC Severity

The average number of days lost (where reported) for each lost work day case.

4.1 Fatalities

The distribution of company and contractor fatal incidents and fatalities between the functions is shown for the years 2021-2025.


Table 39: Fatalities and fatal incidents by function (2021-2025)

Function	Fatal incidents					Fatalities				
	2021	2022	2023	2024	2025	2021	2022	2023	2024	2025
Exploration	0	1	0	0	0	0	1	0	0	0
Drilling	7	7	2	6	8	7	8	2	6	9
Production	5	11	10	13	20	5	13	13	19	31
Construction	3	4	2	1	4	8	4	4	1	4
Unspecified	0	6	3	1	8	0	7	8	6	8
OVERALL	15	29	17	21	40	20	33	27	32	52

4.2 FAR, TRIR, and LTIR five-year rolling averages

In order to smooth out variability in the annual values for TRIR, FAR, and LTIR by function, five-year rolling averages are computed which should provide a more reliable indicator of performance trends.

Figure 62:



For calculations of TRIR, submissions without information on medical treatment cases were removed, leaving a database of 3,535 million hours, almost 92% of the database in 2025. See [Appendix A](#) for more details.

Figure 63:





Figure 64:



4.3 Severity of LWDC

The overall average number of days lost per lost work day case (LWDC) is 42.3 in 2025 (45.3 in 2024).

The severity of LWDCs is the highest in the Drilling Function (46 days lost per LWDC in 2025). This is a 23% decrease compared with the average for the previous five-year period.


Data table A3 in [Appendix A](#) provides further information on the proportion of the database that can be used for LWDC severity. 87% of the data submitted for Construction and 84% of the data submitted for Unspecified were usable for this metric, in comparison with only 55% of equivalent data for Exploration, 59% for Drilling, and 69% for Production.

See [Section 2.8](#) for additional information and [Section 3.6](#) for LWDC severity by region.

Table 30: Severity of lost work day cases by function (2025 compared with 2020-2024)

Function	Severity of LWDC (average days lost per LWDC)			2025 relative to 2020-2024	2025 relative to 2024
	2020-2024	2024	2025		
Exploration	32.5	42.0	38.5	19% higher	8% lower
Drilling	59.2	51.8	45.5	23% lower	12% lower
Production	40.5	44.6	44.1	9% higher	1% lower
Construction	50.8	39.6	39.9	21% lower	1% higher
Unspecified	44.4	44.5	36.3	18% lower	18% lower
OVERALL	46.4	45.3	42.3	9% lower	7% lower

Figure 65:



4.4 Exploration performance

Total recordable injury rate – exploration

Figures 66 and 67 show the total recordable injury rate (TRIR) for companies and contractors for exploration related activities in different regions of the world. The 2025 result is compared with average TRIR results in the previous five-year period.

54 million work hours (72% of reported exploration work hours) were used in this analysis, of which company activities represent 29% and contractor activities represent 71%. This represents an increase of 22 million work hours compared with 2024 (33 million work hours in 2024: 37% company, 63% contractor).

In 2025, the overall TRIR values for companies and contractors engaged in exploration activities are 0.32 and 0.31 respectively; the overall average TRIR for exploration activities is 0.31.

Further information on exploration TRIR by region is available in [Appendix B - Table B.36](#).

 Definitions


Exploration

Geophysical, seismographic, and geological operations, including their administrative and engineering aspects, construction, maintenance, materials supply and transportation of personnel and equipment (excluding drilling).

Figure 66:



Figure 67:



Lost time injury rate – exploration

Figures 68 and 69 show the lost time injury rate (LTIR) for companies and contractors for exploration related activities in different regions of the world. The 2025 result is compared with average LTIR results in the previous five-year period.

75 million work hours (100% of reported exploration work hours) were used in this analysis, of which company activities represent 24% and contractor activities represent 76% (26% company, 74% contractor in 2024). This represents an increase of 20 million work hours compared with 2024.

In 2025, the overall LTIR values for companies and contractors engaged in exploration activities are 0.05 and 0.12 respectively; the overall average LTIR for exploration activities is 0.11.

Further information on exploration LTIR by region is available in [Appendix B](#) - Table B.37.

Figure 68:




Figure 69:



4.5 Drilling performance

Total recordable injury rate – drilling

Figures 70 and 71 show the total recordable injury rate (TRIR) for companies and contractors for drilling related activities in different regions of the world. The 2025 result is compared with average TRIR results in the previous five-year period.

489 million work hours (93% of reported drilling work hours) were used in this analysis, of which company activities represent 10% and contractor activities represent 90%. This represents a decrease of 175 million work hours compared with 2024 (664 million work hours in 2024: 18% company, 82% contractor).

In 2025, the overall TRIR values for companies and contractors engaged in drilling activities are 0.45 and 0.98 respectively; the overall average TRIR for drilling activities is 0.92.

Further information on drilling TRIR by region is available in [Appendix B - Table B.38](#).

Definitions


Drilling

All exploration, appraisal and production drilling, and workover as well as their administrative, engineering, construction, materials supply and transportation aspects. It includes site preparation, rigging up and down, and restoration of the drilling site upon work completion. Drilling includes all exploration, appraisal and production drilling.

Figure 70:



Figure 71:



Lost time injury rate – drilling

Figures 72 and 73 show the lost time injury rate (LTIR) for companies and contractors for drilling related activities in different regions of the world. The 2025 result is compared with average LTIR results in the previous five-year period.

526 million work hours (100% of reported drilling work hours) were used in this analysis, of which company activities represent 14% and contractor activities represent 86% (21% company, 79% contractor in 2024). This represents a decrease of 188 million work hours compared with 2024.

In 2025, the overall LTIR values for companies and contractors engaged in drilling activities are 0.22 and 0.31 respectively; the overall average LTIR for drilling activities is 0.30.

Further information on drilling LTIR by region is available in [Appendix B - Table B.39](#).

Figure 72:




Figure 73:



4.6 Production performance

Total recordable injury rate – production

Figures 74 and 75 show the total recordable injury rate (TRIR) for companies and contractors for production related activities, in different regions of the world. The 2025 result is compared with average TRIR results in the previous five-year period.

1,579 million work hours (91% of reported production work hours) were used in this analysis, of which company activities represent 25% and contractor activities represent 75%. This represents a decrease of 134 million work hours compared with 2024 (1,712 million work hours in 2024: 28% company, 72% contractor).

In 2025, the overall TRIR values for companies and contractors engaged in production activities are 0.81 and 0.80 respectively; the overall average TRIR for production activities is 0.80.

Further information on production TRIR by region is available in [Appendix B](#) - Table B.40.

 Definitions


Production

Petroleum and natural gas producing operations, including their administrative and engineering aspects, minor construction, repairs, maintenance and servicing, materials supply, and transportation of personnel and equipment. It covers all mainstream production operations including wireline. It does not cover production drilling and workover. See [Appendix E - Glossary](#) for details.

Figure 74:



Figure 75:



Lost time injury rate – production

Figures 76 and 77 show the lost time injury rate (LTIR) for companies and contractors for production related activities, in different regions of the world. The 2025 result is compared with average LTIR results in the previous five-year period.

1,741 million work hours (100% of reported production work hours) were used in this analysis, of which company activities represent 28% and contractor activities represent 72% (30% company, 70% contractor in 2024). This represents a decrease of 106 million work hours compared with 2024.

In 2025, the overall LTIR values for companies and contractors engaged in production activities are 0.32 and 0.30 respectively; the overall average LTIR for production activities is 0.31.

Further information on production LTIR by region is available in [Appendix B](#) - Table B.41.

Figure 76:





Figure 77:



4.7 Construction performance

The company and contractor results for 2025 construction performance are presented below.

Construction activities are predominately conducted by contractors therefore the work hours reported for contractors are much greater than those reported for company employees. Refer to [Appendix B](#) for detailed information.

Total recordable injury rate – construction

Figures 78 and 79 show the total recordable injury rate (TRIR) for companies and contractors for construction related activities in different regions of the world. The 2025 result is compared with average TRIR results in the previous five-year period.

746 million work hours (almost 100% of reported construction work hours) were used in this analysis, of which company activities represent 8% and contractor activities represent 92%. This represents an increase of 54 million work hours compared with 2024 (693 million work hours in 2024: 7% company, 93% contractor).

In 2025, the overall TRIR values for companies and contractors engaged in construction activities are 0.43 and 0.63 respectively; the overall average TRIR for construction activities is 0.62.

Further information on construction TRIR by region is available in [Appendix B](#) - Table B.42.

Definitions

Construction

All major construction, fabrication activities and also disassembly, removal and disposal (decommissioning) at the end of the facility life. Includes construction of process plant, yard construction of structures, offshore installation, hook-up and commissioning, and removal of redundant process facilities.

Figure 78:




Figure 79:



Lost time injury rate – construction

Figures 80 and 81 show the lost time injury rate (LTIR) for companies and contractors for construction related activities in different regions of the world. The 2025 result is compared with average LTIR results in the previous five-year period.

748 million work hours (100% of reported construction work hours) were used in this analysis, of which company activities represent 8% and contractor activities represent 92% (9% company, 91% contractor in 2024). This represents a decrease of 56 million work hours compared with 2024.


In 2025, the overall LTIR values for companies and contractors engaged in construction activities are 0.12 and 0.15 respectively; the overall average LTIR for construction activities is 0.15.

Further information on construction LTIR by region is available in [Appendix B](#) - Table B.43.

Figure 80:



Figure 81:



4.8 Unspecified performance

Total recordable injury rate – unspecified

Figures 82 and 83 show the total recordable injury rate (TRIR) for companies and contractors for activities categorized as 'unspecified' in different regions of the world. The 2025 result is compared with average TRIR results in the previous five-year period.

667 million work hours (87% of reported unspecified work hours) were used in this analysis, of which company activities represent 36% and contractor activities represent 64%. This represents a decrease of 27 million work hours compared with 2024 (694 million work hours in 2024: 38% company, 62% contractor).

In 2025, the overall TRIR values for companies and contractors engaged in activities where the work function was not specified are 0.37 and 0.94 respectively; the overall average TRIR for unspecified activities is 0.73.

Further information on unspecified TRIR by region is available in [Appendix B](#) - Table B.44.

Definitions

Unspecified

Unspecified is used for the entry of data associated with office personnel whose work hours and incident data cannot be reasonably assigned to the administrative support of one of the function groupings of exploration, drilling, production, or construction. Corporate overhead support personnel, such as finance or human resources staff, may be examples where work hours cannot be specifically assigned to a particular function. All other data that are not separated out by function are reported as 'unspecified'.

Note: Data for companies that did not split their data submission by work function are included in the 'unspecified' function.

Figure 82:



Figure 83:



Lost time injury rate – unspecified

Figures 84 and 85 show the lost time injury rate (LTIR) for companies and contractors for activities categorized as 'unspecified' in different regions of the world. The 2025 result is compared with average LTIR results in the previous five-year period.

763 million work hours (100% of reported unspecified work hours) were used in this analysis, of which company activities represent 36% and contractor activities represent 64% (37% company, 63% contractor in 2024). This represents an increase of 27 million work hours compared with 2024.

In 2025, the overall LTIR values for companies and contractors engaged in activities where the work function was not specified are 0.13 and 0.25 respectively; the overall average LTIR for unspecified activities is 0.21.

Reported under the 'unspecified' function in 2025 were:

- 3 company and 5 contractor fatalities
- 32 company and 118 contractor lost work day cases

Reported under the 'unspecified' function from 2020 to 2024 were:

- 3 company and 21 contractor fatalities
- 131 company and 307 contractor lost work day cases

Further information on unspecified LTIR by region is available in [Appendix B - Table B.45](#).

Figure 84:




Figure 85:



See [Appendix B - Section 4](#) for data tables.

5. Results by Company

5.1 Overall company results

This section compares the safety performance of individual companies with each other and with their performance in previous years.

For reasons of anonymity each of the companies that has contributed relevant data and is to be included in this analysis has been allocated a unique code letter (A to BBB). These codes change every year in line with LTIR performance. 3 companies were excluded from this analysis because they did not report both company and contractor data. Results for 53 of the 56 participating companies are therefore shown in this section. In 2025, IOGP Member Companies reported 44 contractor and 8 company employee fatalities.

 Definitions

Fatal accident rate (FAR)

The number of company/contractor fatalities per 100 million hours worked.

Total recordable injury rate (TRIR)

The number of recordable injuries (fatalities + lost work day cases + restricted work day cases + medical treatment cases (MTC)) per million hours worked. Note when MTC or RWDC are not reported by a company for a country the associated work hours, fatalities, lost work day cases, restricted work day cases and medical treatment cases are excluded from TRIR calculations.


The number of lost time injuries (fatalities + lost work day cases) per million hours worked.

5.1.1 Fatal accident rate

In Figure 86, the fatal accident rate (FAR) is presented for those companies that, with their contractors, reported more than 50 million work hours. 21 companies met this criterion in 2025, compared with 22 companies in 2024. Companies are presented in rank order of company-with-contractor FAR. The analysis shows that:

- 13 of the 21 companies with their contractors had a lower FAR than the average for companies with contractors reporting more than 50 million work hours (1.27).
- 14 of the 21 companies suffered one or more fatalities.
- 7 of the 21 companies reported no fatalities.

Figure 86:




5.1.2 Total recordable injury rate

The total recordable injury rate (TRIR) for companies together with their contractors is presented below. Data are only included where restricted work day cases (RWDC) and medical treatment cases (MTC) are reported. 50 of the 53 companies that reported both company and contractor data qualified for inclusion in this section. Details of results are tabulated in [Appendix B](#).

In 7 instances, contractors achieved a lower TRIR than the companies they were employed by.


Figure 87 shows the TRIR for companies alone, plotted alongside the TRIR for company and contractors jointly, in rank order of the company-with-contractor TRIR.

Figure 87:



In Figure 88, the TRIR for contractors alone is plotted alongside the TRIR for company and contractors jointly, in rank order of the company-with-contractor TRIR.


Figure 88:



In Figure 89, the TRIR is presented for those companies that, with their contractors, reported more than 50 million work hours, in rank order of the company-with-contractor TRIR. 19 companies met this criterion in 2025, compared with 21 in 2024.

8 of the 19 companies with their contractors had a lower TRIR than the overall average for companies with their contractors reporting more than 50 million work hours (0.72).


Figure 89:



The remaining 31 companies which, with their contractors, reported less than 50 million work hours are presented below, in rank order of the company-with-contractor TRIR.

15 of the 31 companies with their contractors had a lower TRIR than the overall average for smaller companies with contractors (1.11).

Figure 90:



5.1.3 Lost time injury rate


The lost time injury rate (LTIR) for companies together with their contractors is presented below. The incidence of a fatality in either company or contractor operations is indicated (*).

53 of the 56 participating companies (A to BBB) contributed both company and contractor data, although not always for every country in which operations were conducted. Data for all 53 companies that submitted both company and contractor data are therefore included in this section. Detailed results are tabulated in [Appendix B](#). The analysis shows that:

- 47 of the 53 companies with their contractors delivered a LTIR of less than 1.
- 17 of the companies presented below suffered one or more fatality.
- In 6 instances, contractors achieved a lower LTIR than the companies they were employed by.
- 10 companies reported an LTIR of zero for company and contractors combined.


Figure 91 shows the lost time injury rate (LTIR) for companies alone, plotted alongside the LTIR for company and contractors jointly, in rank order of the company-with-contractor LTIR.

Figure 91:



In Figure 92, the LTIR for contractors alone is plotted alongside the LTIR for company and contractors jointly, in rank order of the company-with-contractor LTIR.


Figure 92:



In Figure 93, the LTIR is presented for those companies that, with their contractors, reported more than 50 million work hours, in rank order of the company-with-contractor LTIR. 21 companies met this criterion in 2025, compared with 22 in 2024. The analysis shows that:

- 13 of the 21 companies with their contractors had a lower LTIR than the overall average for companies with their contractors reporting more than 50 million work hours (0.23).
- 14 of the 21 companies suffered one or more fatalities.


Figure 93:



The remaining 32 companies which, with their contractors, reported less than 50 million work hours are presented in Figure 90, in rank order of the company-with-contractor LTIR.

- 20 of the 32 companies with their contractors had a lower LTIR than the overall average for smaller companies with contractors (0.41).
- 3 of the 32 smaller companies presented below suffered one or more fatalities.

Figure 94:



5.2 Company results by function

Results of companies, together with their contractors, have been analysed by function to allow more in-depth benchmarking between companies. The TRIR indicator has been selected, and the ranked results are shown in the following charts. Only companies that provided data by function are included, and then only those companies that reported more than 100,000 hours worked. Results against smaller numbers of hours would not have statistical significance. The company code letters are the same as used elsewhere in this section.

Exploration was the only function where the top quartile company with contractors shows a TRIR of zero.

TRIR results by function can be found in [Appendix B - Table B.47](#).

Figure 95:




Figure 96:




Figure 97:





Figure 98:



See [Appendix B - Section 5](#) for data tables.

Appendix A - Database dimensions

Figure A1:




Table A.1: Work hours reported by data type and operations (2025)

Type	Work hours reported (thousands)		
	Onshore	Offshore	Overall
Company	686,845	219,478	906,324
Contractor	2,217,692	730,605	2,948,298
OVERALL	2,904,538	950,084	3,854,622

The database for the year 2025 covers 3,854,622,000 work hours reported in the upstream sector of the oil and gas industry. The database is 7% smaller than it was in 2024.

- 75% of the hours reported were associated with onshore activities, 25% with offshore activities.
- 87 countries are represented in the database, the same number as in the 2024 database. Countries are listed in the 'Countries' section.
- 56 companies contributed data, of which 53 companies contributed contractor statistics, though not in every case for each country of operation.
- Of the 56 companies, 50 had contributed data in 2024 which accounted for 91% of the database in 2024 and 94% of the database in 2025. 48 of the companies submitting 2025 data had also provided data in 2023.
- 15 of the companies contributed 75% of the hours. 5 companies covered 40% of the hours, and the largest contributor accounted for 12%.
- 24% of the reported work hours were related to company personnel and 76% were related to contractors.

A summary of the key elements of the database is shown in the table at the end of this section.

Figure A2:





Figure A3:



'Unspecified (as a work function)' is used for the entry of data associated with office personnel whose work hours and incident data cannot be reasonably assigned to the administrative support of one of the function groupings of exploration, drilling, production or construction. Corporate overhead support function personnel such as finance or human resources staff may be examples where work hours cannot be specifically assigned to a particular function. All other data that are not separated out by function are reported as 'unspecified'.

Figure A4:





Figure A5:



Proportion of database used in analysis

For calculations of fatal accident rate (FAR, fatal incidents per 100 million work hours), and lost time injury rate (LTIR):

- All hours in the database were used for all regions and work functions.

For calculations of TRIR:

- Submissions without information on medical treatment cases were filtered out, leaving a database of 3,535 million hours, 92% of the database.
- In 2024, the TRIR database was 3,795 million hours, 91% of the total database.

For calculations of lost work day case severity:

- Submissions without information on days off work were filtered out, leaving a database of 2,853 million hours, 74% of the total database.
- In 2024, this database was 3,507 million hours, 84% of the total database.

For calculations of restricted work day case severity:

- Submissions without information on days assigned to restricted activities were filtered out, leaving a database of 2,203 million hours (57% of the total database), and 475 restricted work day cases.
- In 2024, this database was 3,085 million hours, 74% of the total database.

More detailed information is shown in the data tables below.

Table A.2: Percentage of reported work hours included in analyses by region 2025

Region	Percentage of reported work hours included in analysis		
	TRIR	LWDC severity	RWDC severity
Africa	100%	93%	70%
Asia/Australasia	100%	51%	47%
Europe	95%	57%	48%
Middle East	100%	86%	85%
North America	67%	56%	27%
Russia & Central Asia	60%	93%	52%
South & Central America	100%	93%	32%

Table A.3: Percentage of reported work hours included in analyses by function 2025

Function	Percentage of reported work hours included in analysis		
	TRIR	LWDC severity	RWDC severity
Exploration	72%	55%	43%
Drilling	93%	59%	40%
Production	91%	69%	47%
Construction	100%	87%	78%
Unspecified	87%	84%	73%

Table A.4: Percentage of reported RWDC included in RWDC severity calculations 2025

Category	Percentage of reported RWDC included in RWDC severity calculations
Overall	73%
Company	78%
Contractor	72%
Onshore	75%
Offshore	69%

See [Appendix B - Database dimensions](#) for data tables.

Appendix B - Data tables

Table B.1: Summary of 2025 data by region

Region	Data type	Operations	Hours worked (thousands)	Fatalities	LWDCs (number)	RWDCs (number)	MTCs (number)	FAR	TRIR	LTIR
Africa	Company	Onshore	47,360	0	3	4	3	0.00	0.21	0.06
Africa	Company	Offshore	15,469	1	2	2	1	6.46	0.39	0.19
Africa	Contractor	Onshore	224,748	2	21	11	41	0.89	0.33	0.10
Africa	Contractor	Offshore	106,962	5	40	29	43	4.67	1.09	0.42
Africa	SUBTOTAL	SUBTOTAL	394,541	8	66	46	88	2.03	0.53	0.19
Asia/Australasia	Company	Onshore	143,744	1	9	30	14	0.70	0.38	0.07
Asia/Australasia	Company	Offshore	86,428	2	6	16	10	2.31	0.39	0.09
Asia/Australasia	Contractor	Onshore	406,921	12	34	89	89	2.95	0.55	0.11
Asia/Australasia	Contractor	Offshore	149,124	3	31	61	58	2.01	1.03	0.23
Asia/Australasia	SUBTOTAL	SUBTOTAL	786,218	18	80	196	171	2.29	0.59	0.12
Europe	Company	Onshore	75,382	0	29	6	17	0.00	0.72	0.38
Europe	Company	Offshore	23,159	0	28	7	30	0.00	2.85	1.21
Europe	Contractor	Onshore	43,826	0	56	17	26	0.00	2.29	1.28
Europe	Contractor	Offshore	72,670	1	106	49	104	1.38	3.55	1.47
Europe	SUBTOTAL	SUBTOTAL	215,038	1	219	79	177	0.47	2.22	1.02
Middle East	Company	Onshore	110,151	0	10	6	18	0.00	0.31	0.09
Middle East	Company	Offshore	19,197	0	1	2	1	0.00	0.21	0.05
Middle East	Contractor	Onshore	915,818	8	102	116	145	0.87	0.41	0.12
Middle East	Contractor	Offshore	189,068	0	23	11	14	0.00	0.25	0.12
Middle East	SUBTOTAL	SUBTOTAL	1,234,235	8	136	135	178	0.65	0.37	0.12
North America	Company	Onshore	147,042	2	35	18	38	1.36	0.90	0.25
North America	Company	Offshore	40,457	0	26	0	6	0.00	2.14	0.64
North America	Contractor	Onshore	404,084	3	89	114	240	0.74	1.44	0.23
North America	Contractor	Offshore	52,856	0	13	24	36	0.00	2.12	0.25
North America	SUBTOTAL	SUBTOTAL	644,440	5	163	156	320	0.78	1.41	0.26
Russia & Central Asia	Company	Onshore	115,664	1	35	4	48	0.86	1.14	0.31
Russia & Central Asia	Company	Offshore	18,032	1	4	0	4	5.55	0.50	0.28
Russia & Central Asia	Contractor	Onshore	91,281	6	31	7	17	6.57	0.82	0.41
Russia & Central Asia	Contractor	Offshore	5,894	0	3	1	4	0.00	1.36	0.51
Russia & Central Asia	SUBTOTAL	SUBTOTAL	230,872	8	73	12	73	3.47	0.96	0.35
South & Central America	Company	Onshore	47,500	0	6	0	3	0.00	0.19	0.13
South & Central America	Company	Offshore	16,733	0	9	3	3	0.00	0.90	0.54
South & Central America	Contractor	Onshore	131,011	4	35	8	26	3.05	0.56	0.30
South & Central America	Contractor	Offshore	154,030	0	129	15	127	0.00	1.76	0.84
South & Central America	SUBTOTAL	SUBTOTAL	349,275	4	179	26	159	1.15	1.05	0.52
TOTAL	Company	Onshore	686,845	4	127	68	141	0.58	0.54	0.19
TOTAL	Company	Offshore	219,478	4	76	30	55	1.82	0.80	0.36
TOTAL	Contractor	Onshore	2,217,692	35	368	362	584	1.58	0.64	0.18
TOTAL	Contractor	Offshore	730,605	9	345	190	386	1.23	1.29	0.48
GRAND TOTAL	TOTAL	TOTAL	3,854,622	52	916	650	1,166	1.35	0.76	0.25

Table B.2: Summary of 2025 data overall

Operations	Hours worked (thousands)	Fatalities	LWDCs (number)	RWDCs (number)	MTCs (number)	FAR	TRIR	LTIR
Onshore	2,904,538	39	495	430	725	1.34	0.62	0.18
Offshore	950,084	13	421	220	441	1.37	1.19	0.46
OVERALL	3,854,622	52	916	650	1,166	1.35	0.76	0.25
Company	906,324	8	203	98	196	0.88	0.61	0.23
Contractor	2,948,298	44	713	552	970	1.49	0.80	0.26

Table B.3: Summary of 2025 data by function

Function	Data type	Operations	Hours worked (thousands)	Fatalities	LWDCs (number)	RWDCs (number)	MTCs (number)	FAR	TRIR	LTIR
Exploration	Company	Onshore	15,466	0	1	0	4	0.00	0.39	0.06
Exploration	Company	Offshore	2,773	0	0	0	0	0.00	0.00	0.00
Exploration	Contractor	Onshore	36,577	0	3	1	0	0.00	0.16	0.08
Exploration	Contractor	Offshore	20,396	0	4	1	4	0.00	0.45	0.20
Exploration	SUBTOTAL	SUBTOTAL	75,214	0	8	2	8	0.00	0.31	0.11
Drilling	Company	Onshore	50,955	0	10	4	11	0.00	0.47	0.20
Drilling	Company	Offshore	22,034	0	6	1	1	0.00	0.38	0.27
Drilling	Contractor	Onshore	293,873	7	67	61	116	2.38	0.86	0.25
Drilling	Contractor	Offshore	159,590	2	65	42	82	1.25	1.20	0.42
Drilling	SUBTOTAL	SUBTOTAL	526,453	9	148	108	210	1.71	0.92	0.30
Production	Company	Onshore	332,461	2	81	32	93	0.60	0.74	0.25
Production	Company	Offshore	149,343	2	67	20	46	1.34	0.96	0.46
Production	Contractor	Onshore	902,138	21	136	107	216	2.33	0.54	0.17
Production	Contractor	Offshore	357,249	6	217	87	191	1.68	1.43	0.62
Production	SUBTOTAL	SUBTOTAL	1,741,193	31	501	246	546	1.78	0.80	0.31
Construction	Company	Onshore	38,778	0	4	1	9	0.00	0.36	0.10
Construction	Company	Offshore	20,241	1	2	3	5	4.94	0.54	0.15
Construction	Contractor	Onshore	573,227	3	78	112	142	0.52	0.58	0.14
Construction	Contractor	Offshore	116,015	0	25	20	59	0.00	0.90	0.22
Construction	SUBTOTAL	SUBTOTAL	748,263	4	109	136	215	0.53	0.62	0.15
Unspecified	Company	Onshore	249,183	2	31	31	24	0.80	0.36	0.13
Unspecified	Company	Offshore	25,085	1	1	6	3	3.99	0.44	0.08
Unspecified	Contractor	Onshore	411,875	4	84	81	110	0.97	0.79	0.21
Unspecified	Contractor	Offshore	77,353	1	34	40	50	1.29	1.62	0.45
Unspecified	SUBTOTAL	SUBTOTAL	763,497	8	150	158	187	1.05	0.73	0.21
TOTAL	Company	Onshore	686,845	4	127	68	141	0.58	0.54	0.19
TOTAL	Company	Offshore	219,478	4	76	30	55	1.82	0.80	0.36
TOTAL	Contractor	Onshore	2,217,692	35	368	362	584	1.58	0.64	0.18
TOTAL	Contractor	Offshore	730,605	9	345	190	386	1.23	1.29	0.48
GRAND TOTAL	TOTAL	TOTAL	3,854,622	52	916	650	1,166	1.35	0.76	0.25

The following data are presented in relation to the sections where they were used.

Section 2 Overall results

Table B.4: Fatal accident rate (2016-2025)

Year	Company	Contractor	Overall	Onshore	Offshore
2016	0.90	1.97	1.73	1.50	2.37
2017	1.02	1.13	1.10	1.10	1.11
2018	0.31	1.20	1.01	1.02	0.97
2019	0.46	0.92	0.82	0.78	0.95
2020	0.56	0.54	0.55	0.42	0.92
2021	0.29	0.90	0.75	0.79	0.61
2022	0.30	1.62	1.28	1.27	1.29
2023	0.68	0.87	0.82	0.90	0.59
2024	0.57	0.84	0.77	0.56	1.31
2025	0.88	1.49	1.35	1.34	1.37

Table B.5: Fatal incident rate (2016-2025)

Year	Company	Contractor	Overall	Onshore	Offshore
2016	0.45	1.17	1.00	1.08	0.79
2017	1.02	1.00	1.00	1.05	0.86
2018	0.31	1.04	0.88	0.85	0.97
2019	0.30	0.84	0.72	0.68	0.83
2020	0.56	0.44	0.47	0.37	0.77
2021	0.29	0.65	0.56	0.54	0.61
2022	0.15	1.46	1.12	1.11	1.15
2023	0.45	0.54	0.52	0.53	0.47
2024	0.57	0.48	0.50	0.47	0.61
2025	0.88	1.09	1.04	1.03	1.05

Table B.5A: Exposure hours used in the calculation of FAR and FIR

Year	Company	Contractor	Overall	Onshore	Offshore
2016	667,335	2,228,286	2,895,621	2,134,946	760,675
2017	688,779	2,310,260	2,999,039	2,184,775	814,264
2018	653,764	2,412,586	3,066,350	2,244,676	821,674
2019	657,258	2,381,094	3,038,352	2,193,257	845,095
2020	708,712	1,835,489	2,544,201	1,891,036	653,165
2021	686,668	1,992,358	2,679,026	2,021,601	657,425
2022	659,717	1,919,283	2,579,000	1,883,492	695,508
2023	881,802	2,409,580	3,291,382	2,437,811	853,571
2024	1,060,726	3,098,151	4,158,877	3,009,731	1,149,146
2025	906,324	2,948,298	3,854,622	2,904,538	950,084

Table B.6: Fatalities by cause (2025)

Cause	Company	Contractor	Overall	Onshore	Offshore	% of total
Assault or violent act	0	4	4	4	0	7.7
Aviation accident	0	3	3	3	0	5.8
Caught in, under or between (excl. dropped objects)	0	9	9	7	2	17.3
Confined space	0	0	0	0	0	
Cut, puncture, scrape	0	0	0	0	0	
Dropped objects	1	7	8	7	1	15.4
Explosion, fire or burns	1	5	6	2	4	11.5
Exposure electrical	0	2	2	2	0	3.8
Exposure noise, chemical, biological, vibration, extreme temperature	0	1	1	1	0	1.9
Falls from height	0	5	5	4	1	9.6
Overexertion, strain	0	0	0	0	0	
Pressure release	0	0	0	0	0	
Slips and trips (at same height)	0	0	0	0	0	
Struck by (not dropped object)	1	7	8	7	1	15.4
Water related, drowning	3	1	4	1	3	7.7
Unspecified - Other	2	0	2	1	1	3.8
OVERALL	8	44	52	39	13	

Table B.7: Fatalities by activity (2025)

Cause	Company	Contractor	Overall	Onshore	Offshore	% of total
Construction, commissioning, decommissioning	1	3	4	3	1	7.7
Diving (incl. decompression), subsea, ROV	0	0	0	0	0	
Drilling, workover, well operations	0	9	9	8	1	17.3
Excavation, trenching, ground disturbance	0	0	0	0	0	
Lifting, crane, rigging, deck operations	2	4	6	3	3	11.5
Maintenance, inspection, testing	2	12	14	9	5	26.9
Office, warehouse, accommodation, catering	0	0	0	0	0	
Production operations	1	4	5	3	2	9.6
Seismic/survey operations	0	0	0	0	0	
Transport - Air	0	3	3	3	0	5.8
Transport - Land	1	9	10	10	0	19.2
Transport - Water, incl. marine activity	0	0	0	0	0	
Unspecified - other	1	0	1	0	1	1.9
OVERALL	8	44	52	39	13	

Table B.8: Total recordable injury rate (2016-2025)

Year	Company	Contractor	OVERALL	Onshore	Offshore
2016	0.82	1.09	1.03	0.83	1.60
2017	0.78	1.01	0.96	0.80	1.37
2018	0.72	1.06	0.99	0.88	1.27
2019	0.67	0.98	0.92	0.81	1.20
2020	0.49	0.78	0.70	0.59	1.01
2021	0.51	0.85	0.77	0.61	1.23
2022	0.61	0.99	0.90	0.78	1.21
2023	0.57	0.94	0.84	0.75	1.11
2024	0.56	0.89	0.81	0.73	1.04
2025	0.61	0.80	0.76	0.62	1.19

Table B.8A: Exposure hours used in the calculation of TRIR

Year	Company	Contractor	OVERALL	Onshore	Offshore
2016	662,818	2,227,323	2,890,141	2,129,739	760,402
2017	639,720	2,283,689	2,923,409	2,112,668	810,741
2018	653,764	2,412,480	3,066,244	2,244,676	821,568
2019	616,171	2,375,066	2,991,237	2,146,142	845,095
2020	649,265	1,792,191	2,441,456	1,791,850	649,606
2021	639,681	1,992,358	2,632,039	1,974,614	657,425
2022	615,716	1,919,004	2,534,720	1,839,491	695,229
2023	881,802	2,409,580	3,291,382	2,437,811	853,571
2024	919,061	2,875,614	3,794,675	2,808,139	986,536
2025	755,793	2,778,731	3,534,525	2,641,083	893,441

Table B.9: Lost time injury rate (2016-2025)

Year	Company	Contractor	OVERALL	Onshore	Offshore
2016	0.24	0.28	0.27	0.20	0.45
2017	0.28	0.26	0.27	0.22	0.41
2018	0.25	0.26	0.26	0.22	0.37
2019	0.24	0.24	0.24	0.19	0.36
2020	0.20	0.22	0.22	0.17	0.35
2021	0.19	0.24	0.22	0.17	0.40
2022	0.26	0.28	0.28	0.22	0.44
2023	0.22	0.24	0.24	0.19	0.38
2024	0.21	0.24	0.24	0.18	0.39
2025	0.23	0.26	0.25	0.18	0.46

Table B.9A: Exposure hours used in the calculation of LTIR

Year	Company	Contractor	OVERALL	Onshore	Offshore
2016	667,335	2,228,286	2,895,621	2,134,946	760,675
2017	688,779	2,310,260	2,999,039	2,184,775	814,264
2018	653,764	2,412,586	3,066,350	2,244,676	821,674
2019	657,258	2,381,094	3,038,352	2,193,257	845,095
2020	708,712	1,835,489	2,544,201	1,891,036	653,165
2021	686,668	1,992,358	2,679,026	2,021,601	657,425
2022	659,717	1,919,283	2,579,000	1,883,492	695,508
2023	881,802	2,409,580	3,291,382	2,437,811	853,571
2024	1,060,726	3,098,151	4,158,877	3,009,731	1,149,146
2025	906,324	2,948,298	3,854,622	2,904,538	950,084

Table B.10: Lost work day cases by cause (2025)

Cause	Company	Contractor	OVERALL	Onshore	Offshore	% of total
Assault or violent act	0	3	3	3	0	0.3
Caught in, under or between (excl. dropped objects)	33	121	154	80	74	16.8
Cut, puncture, scrape	4	33	37	20	17	4.0
Dropped objects	8	21	29	23	6	3.2
Explosion, fire or burns	5	51	56	26	30	6.1
Exposure electrical	4	4	8	6	2	0.9
Exposure noise, chemical, biological, vibration, extreme temperature	13	23	36	19	17	3.9
Falls from height	13	43	56	30	26	6.1
Overexertion, strain	22	48	70	36	34	7.6
Pressure release	1	6	7	6	1	0.8
Slips and trips (at same height)	50	145	195	114	81	21.3
Struck by (not dropped object)	26	112	138	78	60	15.1
Water related, drowning	1	2	3	0	3	0.3
Unspecified - Other	23	101	124	54	70	13.5
OVERALL	203	713	916	495	421	

Note: dropped objects was introduced as a LWDC cause in 2019.

Table B.11: Lost work day cases by activity (2025)

Activity	Company	Contractor	OVERALL	Onshore	Offshore	% of total
Construction, commissioning, decommissioning	5	119	124	73	51	13.5
Diving (incl. decompression), subsea, ROV	0	4	4	0	4	0.4
Drilling, workover, well operations	19	125	144	98	46	15.7
Excavation, trenching, ground disturbance	2	6	8	8	0	0.9
Lifting, crane, rigging, deck operations	12	65	77	34	43	8.4
Maintenance, inspection, testing	53	120	173	74	99	18.9
Office, warehouse, accommodation, catering	16	46	62	32	30	6.8
Production operations	54	96	150	82	68	16.4
Seismic/survey operations	0	2	2	1	1	0.2
Transport - Land	9	13	22	22	0	2.4
Transport - Water, incl. marine activity	0	13	13	1	12	1.4
Unspecified - other	33	104	137	70	67	15.0
OVERALL	203	713	916	495	421	

Table B.12: Lost work day case severity (2016-2025)

Year	Average number of days lost per LWDC				
	Company	Contractor	OVERALL	Onshore	Offshore
2016	37.6	66.9	61.4	46.9	79.2
2017	40.5	43.0	42.5	45.1	39.0
2018	37.7	54.6	51.5	49.4	54.9
2019	44.8	52.5	50.9	53.8	46.7
2020	40.1	42.9	42.3	39.2	47.6
2021	56.4	51.4	52.4	53.9	50.1
2022	38.3	42.4	41.3	45.4	34.9
2023	42.9	52.5	50.0	46.2	56.1
2024	50.3	43.6	45.3	47.5	42.3
2025	55.0	38.3	42.3	42.7	41.7

Table B.13: Restricted work day case severity (2016-2025)

Year	Average number of days restricted per RWDC				
	Company	Contractor	OVERALL	Onshore	Offshore
2016	14.4	14.4	14.4	13.8	15.6
2017	12.5	18.0	17.2	17.1	17.6
2018	16.7	19.8	19.4	19.9	18.9
2019	23.5	23.7	23.7	25.4	21.4
2020	32.2	25.9	26.4	31.5	19.7
2021	41.2	23.4	26.3	26.3	26.2
2022	31.8	27.9	28.5	27.0	31.0
2023	23.0	24.7	24.5	25.3	22.9
2024	30.0	34.2	33.6	33.1	34.7
2025	22.8	24.7	24.4	22.4	28.5

Table B.14: IOGP Life-Saving Rules allocated to fatal incidents (2025)

Life-Saving Rule	Fatal incidents				
	2021	2022	2023	2024	2025
Bypassing safety controls	0	0	2	1	2
Confined space	0	0	0	2	1
Driving	1	2	3	4	3
Energy isolation	1	4	1	1	4
Hot work	0	3	0	1	2
Line of fire	5	12	2	3	12
Safe mechanical lifting	3	2	2	1	6
Work authorization	0	1	1	3	1
Working at height	4	1	2	2	3
Other issue – no applicable rule	0	4	4	3	5
Unspecified	1	0	0	0	1

Table B.15: IOGP Life-Saving Rules allocated to lost work day cases (2025)

Life-Saving Rule	Lost work day cases				
	2021	2022	2023	2024	2025
Bypassing safety controls	5	5	23	25	13
Confined space	2	7	2	7	6
Driving	7	13	16	33	20
Energy isolation	20	20	22	22	33
Hot work	7	6	4	5	7
Line of fire	109	176	210	215	255
Safe mechanical lifting	42	23	47	46	43
Work authorization	7	17	13	28	24
Working at height	44	37	30	41	42
Other issue – no applicable rule	200	180	140	186	176
Unspecified	137	198	241	338	297

Section 3 Results by region

Table B.16: Fatalities and fatal incidents by region (2021-2025)

Region	Fatalities					Fatal incidents				
	2021	2022	2023	2024	2025	2021	2022	2023	2024	2025
Africa	7	2	5	8	8	2	2	4	3	5
Asia/Australasia	0	7	11	3	18	0	7	5	2	15
Europe	2	0	0	1	1	2	0	0	1	1
Middle East	4	11	4	9	8	4	8	3	6	7
North America	1	4	3	7	5	1	4	3	5	5
Russia & Central Asia	2	3	4	2	8	2	2	2	2	5
South & Central America	4	6	0	2	4	4	6	0	2	2
OVERALL	20	33	27	32	52	15	29	17	21	40

Table B.17: Fatal accident rate by region (2021-2025)

Region	Fatal accident rate (FAR)				
	2021	2022	2023	2024	2025
Africa	2.16	0.54	1.29	1.67	2.03
Asia/Australasia	0.00	1.44	1.94	0.34	2.29
Europe	0.87	0.00	0.00	0.43	0.47
Middle East	0.60	2.17	0.40	0.77	0.65
North America	0.38	1.21	0.78	0.93	0.78
Russia & Central Asia	0.60	0.94	1.29	0.88	3.47
South & Central America	1.14	1.93	0.00	0.48	1.15
OVERALL	0.75	1.28	0.82	0.77	1.35

Table B.18: Total recordable injury rate by region (2021-2025)

Region	Total recordable injury rate (TRIR)				
	2021	2022	2023	2024	2025
Africa	0.39	0.37	0.36	0.42	0.53
Asia/Australasia	0.69	0.77	0.66	0.53	0.59
Europe	1.93	1.82	1.67	2.06	2.22
Middle East	0.30	0.30	0.40	0.44	0.37
North America	1.40	1.61	1.70	1.62	1.41
Russia & Central Asia	0.46	0.60	0.52	0.67	0.96
South & Central America	1.14	1.45	1.62	1.43	1.05
OVERALL	0.77	0.90	0.84	0.81	0.76

Table B.19: Lost time injury rate by region (2021-2025)

Region	Lost time injury rate (LTIR)				
	2021	2022	2023	2024	2025
Africa	0.13	0.11	0.10	0.16	0.19
Asia/Australasia	0.14	0.16	0.14	0.12	0.12
Europe	0.82	0.77	0.68	0.91	1.02
Middle East	0.06	0.09	0.10	0.11	0.12
North America	0.23	0.33	0.35	0.28	0.26
Russia & Central Asia	0.15	0.16	0.17	0.24	0.35
South & Central America	0.42	0.63	0.52	0.46	0.52
OVERALL	0.22	0.28	0.24	0.24	0.25

Table B.20: Work hours reported by region (2016-2025)

Region	Thousand work hours									
	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025
Africa	444,534	489,592	537,130	480,700	322,739	323,847	371,510	388,712	478,530	394,541
Asia/Australasia	745,095	595,521	531,067	594,527	531,985	510,335	486,294	567,832	877,373	786,218
Europe	273,984	248,856	250,880	275,861	233,754	231,120	250,769	256,096	230,398	215,038
Middle East	607,678	754,753	756,946	675,784	591,323	670,571	507,003	1,008,695	1,170,824	1,234,235
North America	325,869	326,804	367,241	369,476	259,026	260,595	331,406	383,252	756,140	644,440
Russia & Central Asia	166,000	235,205	220,906	246,248	283,302	332,910	320,670	309,121	228,189	230,872
South & Central America	332,461	348,308	402,180	395,756	322,072	349,648	311,348	377,671	417,421	349,275
OVERALL	2,895,621	2,999,039	3,066,350	3,038,352	2,544,201	2,679,026	2,579,000	3,291,382	4,158,877	3,854,622

Table B.21: Fatal accident rate five-year rolling average by region (2016-2025)

Region	FAR five-year rolling average									
	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025
Africa	2.50	2.19	1.43	1.52	1.32	1.25	1.13	1.17	1.27	1.53
Asia/Australasia	1.16	1.03	1.06	0.91	0.90	0.43	0.60	0.82	0.81	1.21
Europe	1.85	1.88	1.46	1.44	1.25	0.32	0.32	0.32	0.25	0.34
Middle East	1.01	0.74	0.86	0.90	0.86	0.78	1.03	0.81	0.84	0.78
North America	2.79	1.92	1.72	1.78	1.33	1.20	0.94	1.00	0.85	0.84
Russia & Central Asia	0.87	1.41	1.43	1.34	1.13	1.14	0.78	0.80	0.88	1.34
South & Central America	1.61	1.75	1.08	1.11	0.89	1.05	1.18	0.85	0.67	0.89
OVERALL	1.72	1.48	1.25	1.23	1.05	0.86	0.88	0.84	0.83	0.99

Table B.22: Total recordable injury rate five-year rolling average by region (2016-2025)

Region	TRIR five-year rolling average									
	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025
Africa	0.92	0.79	0.67	0.54	0.46	0.44	0.41	0.38	0.38	0.41
Asia/Australasia	1.01	0.91	0.87	0.78	0.68	0.65	0.65	0.64	0.61	0.63
Europe	2.44	2.34	2.25	2.16	2.09	2.06	2.01	1.91	1.86	1.93
Middle East	0.80	0.70	0.60	0.52	0.46	0.43	0.38	0.37	0.38	0.38
North America	2.40	2.24	2.12	1.94	1.74	1.66	1.59	1.52	1.52	1.55
Russia & Central Asia	0.75	0.62	0.56	0.56	0.50	0.49	0.52	0.52	0.53	0.60
South & Central America	2.69	2.34	1.98	1.60	1.47	1.34	1.34	1.33	1.35	1.34
OVERALL	1.45	1.30	1.17	1.03	0.93	0.88	0.86	0.83	0.81	0.81

Table B.23: Lost time injury rate five-year rolling average by region (2016-2025)

Region	LTIR five-year rolling average									
	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025
Africa	0.26	0.23	0.19	0.15	0.14	0.13	0.13	0.11	0.12	0.14
Asia/Australasia	0.17	0.15	0.16	0.15	0.14	0.13	0.13	0.13	0.13	0.13
Europe	0.84	0.81	0.74	0.74	0.75	0.77	0.77	0.77	0.78	0.83
Middle East	0.18	0.15	0.13	0.11	0.10	0.09	0.08	0.09	0.09	0.10
North America	0.55	0.46	0.40	0.38	0.34	0.31	0.30	0.30	0.29	0.29
Russia & Central Asia	0.23	0.20	0.17	0.15	0.16	0.16	0.16	0.16	0.18	0.20
South & Central America	0.73	0.71	0.63	0.54	0.51	0.48	0.48	0.48	0.48	0.51
OVERALL	0.38	0.33	0.29	0.27	0.25	0.24	0.24	0.24	0.24	0.24

Table B.24: Severity of lost work day cases by region (2021 - 2025)

Region	Average days lost per LWDC				
	2021	2022	2023	2024	2025
Africa	24.5	39.6	43.8	40.1	21.7
Asia/Australasia	59.4	40.8	40.3	37.4	50.3
Europe	35.9	38.3	50.0	43.9	49.0
Middle East	58.5	23.6	25.0	22.9	26.5
North America	29.5	58.9	57.5	59.7	56.7
Russia & Central Asia	79.3	54.8	70.3	52.8	64.2
South & Central America	64.9	37.8	58.4	54.6	33.8
OVERALL	52.4	41.3	50.0	45.3	42.3

Table B.25: Total recordable injury rate by country (2023-2025)

Note: data only included in TRIR calculations where medical treatment cases are reported.

Countries with less than 50,000 reported work hours or with fewer than 2 companies reporting in 2025 or the reporting year are excluded.

Iran and Russia are excluded.

Region	Country	Total recordable injury rate (TRIR)		
		2023	2024	2025
Africa	Cameroon	no data	1.22	2.67
Africa	Gabon	1.03	2.72	1.85
Africa	Mauritania	0	1.81	1.71
Africa	Equatorial Guinea	0.76	1.17	1.58
Africa	Namibia	1.79	1.17	1.17
Africa	Tunisia	1.01	0.24	0.98
Africa	Angola	0.55	0.8	0.68
Africa	Ghana	0.15	0.15	0.67
Africa	AFRICA AVERAGE	0.36	0.42	0.53
Africa	Libya	0.13	0.04	0.4
Africa	Congo	0.21	0.14	0.36
Africa	Ivory Coast	0.24	0.26	0.29
Africa	Nigeria	0.33	0.26	0.27
Africa	Algeria	0.56	0.45	0.22
Africa	Egypt	0.07	0.35	0.14
Africa	Mozambique	0	0	0
Africa	São Tomé and Príncipe	0	no data	0
Africa	Senegal	1.49	0.42	0
Africa	South Africa	0	0	0
Africa	Tanzania	0	0	0
Asia/Australasia	Australia	3.66	4.22	3.44
Asia/Australasia	Japan	2.17	0.99	0.89
Asia/Australasia	Thailand	0.72	0.77	0.61
Asia/Australasia	ASIA/AUSTRALASIA AVERAGE	0.66	0.53	0.59
Asia/Australasia	India	0.51	0.52	0.55
Asia/Australasia	Brunei	1.32	0	0.51
Asia/Australasia	Philippines	1.99	no data	0.47
Asia/Australasia	Malaysia	0.35	0.54	0.27
Asia/Australasia	Papua New Guinea	0.1	0.19	0.25
Asia/Australasia	Singapore	0	0.53	0.24
Asia/Australasia	South Korea	0	10.31	0.2
Asia/Australasia	Indonesia	0.25	0.11	0.17
Asia/Australasia	China	0.05	0.09	0.06
Asia/Australasia	Vietnam	0.73	0	0
Europe	Norway	2.26	2.53	2.75
Europe	Germany	2.95	1.54	2.61
Europe	Cyprus	1.53	3.76	2.47
Europe	EUROPE AVERAGE	1.67	2.06	2.22
Europe	UK	1.1	2.4	2.2
Europe	Netherlands	1.09	1.28	2.03
Europe	Italy	1.25	1.48	1.79
Europe	Denmark	2.11	no data	1.34
Europe	Albania	1.32	0	0
Europe	France	0	1.08	0
Middle East	Kurdistan Region Of Iraq	1.87	1.74	1.26
Middle East	Qatar	0.77	0.84	0.69
Middle East	MIDDLE EAST AVERAGE	0.4	0.44	0.37
Middle East	Iraq	0.2	0.23	0.33
Middle East	Kuwait	0.36	0.28	0.26
Middle East	Oman	0.48	0.5	0.26
Middle East	UAE	0.13	0.14	0.1
Middle East	Turkey	no data	1.19	0
North America	Canada	1.56	1.86	1.83
North America	NORTH AMERICA AVERAGE	1.7	1.62	1.41
North America	USA	1.79	1.58	1.33
North America	Mexico	0.49	0.53	0.56
Russia & Central Asia	Azerbaijan	0.64	1	1.11

Region	Country	Total recordable injury rate (TRIR)		
		2023	2024	2025
Russia & Central Asia	RUSSIA & CENTRAL ASIA AVERAGE	0.52	0.67	0.96
Russia & Central Asia	Kazakhstan	0.46	0.44	0.72
South & Central America	Trinidad and Tobago	1.37	1.08	1.42
South & Central America	Bolivia	0.19	0.36	1.15
South & Central America	Brazil	1.29	1.11	1.15
South & Central America	SOUTH & CENTRAL AMERICA AVERAGE	1.62	1.43	1.05
South & Central America	Peru	0.29	1.14	0.99
South & Central America	Argentina	2.78	2.39	0.61
South & Central America	Colombia	1.31	0	0
South & Central America	Suriname	0.76	0	0
South & Central America	Venezuela	0	0.65	0

Table B.26: Lost time injury rate by country (2023-2025)

Note: Countries with less than 50,000 reported work hours or with fewer than 2 companies reporting in 2025 or the reporting year are excluded.

Iran and Russia are excluded.

Region	Country	Lost time injury rate (LTIR)		
		2023	2024	2025
Africa	Mauritania	0	1.21	1.71
Africa	Namibia	0.36	0	1.17
Africa	Gabon	0.41	1.82	0.85
Africa	Tunisia	0.61	0.39	0.59
Africa	Equatorial Guinea	0.19	0.33	0.4
Africa	Cameroon	no data	0.32	0.31
Africa	Angola	0.05	0.09	0.29
Africa	AFRICA AVERAGE	0.1	0.16	0.19
Africa	Algeria	0.13	0.06	0.11
Africa	Congo	0.06	0.03	0.08
Africa	Nigeria	0.14	0.05	0.08
Africa	Egypt	0.02	0.13	0.03
Africa	Ghana	0.15	0	0
Africa	Ivory Coast	0	0	0
Africa	Libya	0.04	0.04	0
Africa	Mozambique	0	0	0
Africa	São Tomé and Príncipe	0	no data	0
Africa	Senegal	0.25	0	0
Africa	South Africa	0	0	0
Africa	Tanzania	0	0	0
Asia/Australasia	Australia	0.57	0.68	0.6
Asia/Australasia	Singapore	0	0.4	0.24
Asia/Australasia	Japan	0.54	0.2	0.22
Asia/Australasia	South Korea	0	10.31	0.2
Asia/Australasia	India	0.15	0.15	0.14
Asia/Australasia	ASIA/AUSTRALASIA AVERAGE	0.14	0.12	0.12
Asia/Australasia	Malaysia	0.09	0.26	0.11
Asia/Australasia	Thailand	0.09	0.16	0.1
Asia/Australasia	Brunei	0	0	0.09
Asia/Australasia	Indonesia	0.03	0.02	0.04
Asia/Australasia	China	0.03	0.04	0
Asia/Australasia	Papua New Guinea	0	0	0
Asia/Australasia	Philippines	0	no data	0
Asia/Australasia	Vietnam	0	0	0
Europe	Italy	1.08	1.25	1.59
Europe	UK	0.26	0.93	1.12
Europe	Norway	0.9	0.99	1.09
Europe	EUROPE AVERAGE	0.68	0.91	1.02
Europe	Germany	0.87	0.38	0.58
Europe	Netherlands	0.18	0.89	0.56
Europe	Denmark	0.59	no data	0.45
Europe	Albania	0	0	0
Europe	Cyprus	0	0	0
Europe	France	0	0	0
Middle East	Qatar	0.13	0.18	0.19
Middle East	Iraq	0.07	0.08	0.15
Middle East	Kuwait	0.18	0.08	0.12
Middle East	MIDDLE EAST AVERAGE	0.1	0.11	0.12
Middle East	Oman	0.14	0.18	0.05
Middle East	UAE	0.03	0.05	0.05
Middle East	Kurdistan Region Of Iraq	0.14	0.58	0
Middle East	Turkey	no data	0	0
North America	USA	0.42	0.44	0.34
North America	NORTH AMERICA AVERAGE	0.35	0.28	0.26
North America	Mexico	0.25	0.18	0.2
North America	Canada	0.15	0.12	0.1
Russia & Central Asia	Azerbaijan	0.24	0.34	0.39
Russia & Central Asia	RUSSIA & CENTRAL ASIA AVERAGE	0.17	0.24	0.35
Russia & Central Asia	Kazakhstan	0.13	0.17	0.32

Region	Country	Lost time injury rate (LTIR)		
		2023	2024	2025
South & Central America	Brazil	0.66	0.61	0.62
South & Central America	Peru	0.14	0.47	0.58
South & Central America	SOUTH & CENTRAL AMERICA AVERAGE	0.52	0.46	0.52
South & Central America	Bolivia	0.19	0.18	0.38
South & Central America	Trinidad and Tobago	0.31	0.34	0.26
South & Central America	Argentina	0.41	0.24	0.19
South & Central America	Colombia	0.44	0	0
South & Central America	Suriname	0	0	0
South & Central America	Venezuela	0	0	0

Section 4 Results by function

Table B.27: Fatalities and fatal incidents by function (2021-2025)

Function	Fatal incidents					Fatalities				
	2021	2022	2023	2024	2025	2021	2022	2023	2024	2025
Exploration	0	1	0	0	0	0	1	0	0	0
Drilling	7	7	2	6	8	7	8	2	6	9
Production	5	11	10	13	20	5	13	13	19	31
Construction	3	4	2	1	4	8	4	4	1	4
Unspecified	0	6	3	1	8	0	7	8	6	8
OVERALL	15	29	17	21	40	20	33	27	32	52

Table B.28: Exposure hours by function (2021-2025)

Function	Hours (thousands)				
	2021	2022	2023	2024	2025
Exploration	37,838	29,118	42,920	55,709	75,214
Drilling	328,583	326,310	493,511	714,524	526,453
Production	1,326,571	1,267,104	1,499,781	1,847,122	1,741,193
Construction	559,086	461,358	605,228	804,614	748,263
Unspecified	426,948	495,110	649,940	736,907	763,497
OVERALL	2,679,026	2,579,000	3,291,382	4,158,877	3,854,622

Table B.29: Fatal accident rate five-year rolling average by function (2020-2025)

Function	FAR five-year rolling average					
	2020	2021	2022	2023	2024	2025
Exploration	1.04	0.55	1.16	0.55	0.50	0.42
Drilling	2.41	2.47	2.13	1.45	1.33	1.34
Production	1.18	0.76	0.74	0.78	0.77	1.05
Construction	0.48	0.56	0.68	0.71	0.61	0.66
Unspecified	0.61	0.42	0.62	0.73	0.84	0.94
OVERALL	1.05	0.86	0.88	0.84	0.83	0.99

Table B.30: Fatal accident rate by function (2020-2025)

Function	Fatal accident rate (FAR)					
	2020	2021	2022	2023	2024	2025
Exploration	0.00	0.00	3.43	0.00	0.00	0.00
Drilling	1.94	2.13	2.45	0.41	0.84	1.71
Production	0.36	0.38	1.03	0.87	1.03	1.78
Construction	0.18	1.43	0.87	0.66	0.12	0.53
Unspecified	0.55	0.00	1.41	1.23	0.81	1.05
OVERALL	0.55	0.75	1.28	0.82	0.77	1.35

Table B.31: Total recordable injury rate five-year rolling average by function (2020-2025)

Function	TRIR five-year rolling average					
	2020	2021	2022	2023	2024	2025
Exploration	1.06	0.93	0.87	0.68	0.51	0.40
Drilling	1.69	1.62	1.61	1.51	1.26	1.16
Production	1.04	0.94	0.89	0.82	0.81	0.82
Construction	0.65	0.63	0.66	0.66	0.69	0.71
Unspecified	0.54	0.54	0.54	0.57	0.58	0.65
OVERALL	0.93	0.88	0.86	0.83	0.81	0.81

Table B.32: Total recordable injury rate by function (2020-2025)

Function	Total recordable injury rate (TRIR)					
	2020	2021	2022	2023	2024	2025
Exploration	0.87	0.48	0.27	0.47	0.49	0.31
Drilling	1.47	1.33	1.68	1.29	0.91	0.92
Production	0.72	0.79	0.84	0.82	0.85	0.80
Construction	0.49	0.59	0.81	0.75	0.79	0.62
Unspecified	0.42	0.50	0.64	0.66	0.64	0.73
OVERALL	0.70	0.77	0.90	0.84	0.81	0.76

Table B.33: Lost time injury rate five-year rolling average by function (2020-2025)

Function	LTIR five-year rolling average					
	2020	2021	2022	2023	2024	2025
Exploration	0.37	0.41	0.41	0.37	0.24	0.17
Drilling	0.49	0.46	0.45	0.41	0.35	0.32
Production	0.30	0.28	0.28	0.27	0.27	0.28
Construction	0.14	0.14	0.15	0.15	0.15	0.16
Unspecified	0.14	0.13	0.13	0.14	0.16	0.18
OVERALL	0.25	0.24	0.24	0.24	0.24	0.24

Table B.34: Lost time injury rate by function (2020-2025)

Function	Lost time injury rate (LTIR)					
	2020	2021	2022	2023	2024	2025
Exploration	0.42	0.37	0.14	0.21	0.13	0.11
Drilling	0.47	0.40	0.44	0.30	0.27	0.30
Production	0.24	0.25	0.32	0.27	0.26	0.31
Construction	0.12	0.15	0.18	0.15	0.17	0.15
Unspecified	0.12	0.08	0.17	0.18	0.21	0.21
OVERALL	0.22	0.22	0.28	0.24	0.24	0.25

Table B.35: Severity of lost work day cases by function (2020-2025)

Function	Average days lost per LWDC					
	2020	2021	2022	2023	2024	2025
Exploration	33.3	35.2	2.7	32.5	42.0	38.5
Drilling	53.4	70.6	55.0	66.8	51.8	45.5
Production	34.0	45.6	32.9	43.0	44.6	44.1
Construction	47.4	59.6	59.8	57.0	39.6	39.9
Unspecified	44.3	40.0	43.7	46.1	44.5	36.3
OVERALL	42.3	52.4	41.3	50.0	45.3	42.3

Table B.36: Exploration TRIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Exploration TRIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.09	0.00	0.71	0.00	1,038	699
Asia/Australasia	0.00	0.00	0.29	0.22	2,854	4,558
Europe	1.05	0.00	1.41	2.39	2,927	837
Middle East	0.23	0.22	0.17	0.03	4,556	29,352
North America	0.20	4.89	0.71	1.87	613	1,066
Russia & Central Asia	0.17	0.00	0.00	0.00	1,276	248
South & Central America	0.00	0.41	1.86	3.22	2,412	1,862
OVERALL	0.37	0.32	0.66	0.31	15,678	38,624

Table B37: Exploration LTIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Exploration LTIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.09	0.00	0.19	0.00	1,038	699
Asia/Australasia	0.00	0.00	0.12	0.22	2,854	4,558
Europe	1.01	0.00	0.54	0.77	3,529	1,290
Middle East	0.00	0.00	0.00	0.03	4,556	29,352
North America	0.00	0.00	0.07	0.11	2,573	18,962
Russia & Central Asia	0.17	0.00	0.00	0.00	1,276	248
South & Central America	0.00	0.41	0.96	1.07	2,412	1,862
OVERALL	0.29	0.05	0.21	0.12	18,240	56,973

Table B.38: Drilling TRIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Drilling TRIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.48	0.00	0.81	0.62	3,366	37,344
Asia/Australasia	0.14	0.00	0.76	0.37	21,911	154,930
Europe	0.75	0.75	3.38	2.57	6,673	22,943
Middle East	0.31	0.39	0.62	0.54	5,065	117,571
North America	0.46	0.60	2.95	2.75	3,323	55,343
Russia & Central Asia	1.25	3.00	1.08	1.96	3,670	6,112
South & Central America	0.40	0.39	2.52	1.40	5,160	45,146
OVERALL	0.42	0.45	1.43	0.98	49,170	439,393

Table B.39: Drilling LTIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Drilling LTIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.16	0.00	0.20	0.21	3,366	37,344
Asia/Australasia	0.03	0.00	0.20	0.13	21,911	154,930
Europe	0.47	0.14	1.64	0.99	7,188	25,204
Middle East	0.14	0.20	0.17	0.26	5,065	117,571
North America	0.25	0.45	0.47	0.28	26,627	67,152
Russia & Central Asia	0.43	0.54	0.38	0.82	3,670	6,112
South & Central America	0.06	0.00	0.63	0.73	5,160	45,146
OVERALL	0.18	0.22	0.38	0.31	72,989	453,463

Table B.40: Production TRIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Production TRIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.25	0.20	0.43	0.60	24,431	127,635
Asia/Australasia	0.56	0.43	0.62	0.54	83,084	249,616
Europe	1.36	1.78	2.49	3.67	56,594	57,210
Middle East	0.29	0.22	0.29	0.22	71,319	358,660
North America	1.72	1.45	1.24	1.06	49,765	204,627
Russia & Central Asia	0.42	0.99	0.41	0.75	68,606	21,437
South & Central America	0.80	0.52	1.49	1.28	36,455	169,066
OVERALL	0.72	0.81	0.86	0.80	390,257	1,188,253

Table B.41: Production LTIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Production LTIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.09	0.08	0.12	0.22	24,431	127,635
Asia/Australasia	0.12	0.06	0.13	0.11	83,084	249,616
Europe	0.67	0.92	1.00	1.82	58,761	58,821
Middle East	0.09	0.07	0.09	0.09	71,319	358,660
North America	0.40	0.38	0.24	0.19	91,000	229,425
Russia & Central Asia	0.22	0.32	0.12	0.41	116,751	66,163
South & Central America	0.49	0.38	0.54	0.67	36,455	169,066
OVERALL	0.28	0.32	0.26	0.30	481,804	1,259,388

Table B.42: Construction TRIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Construction TRIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.13	0.00	0.40	0.32	5,675	65,786
Asia/Australasia	0.36	0.58	0.59	0.99	17,352	67,759
Europe	0.35	0.29	2.78	2.32	6,851	16,399
Middle East	0.46	0.31	0.42	0.52	12,738	450,800
North America	0.43	0.73	1.65	1.31	2,727	21,365
Russia & Central Asia	1.40	0.84	0.60	0.38	7,104	10,432
South & Central America	0.12	0.16	1.39	0.78	6,152	55,351
OVERALL	0.57	0.43	0.71	0.63	58,602	687,895

Table B.43: Construction LTIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Construction LTIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.04	0.00	0.15	0.15	5,675	65,786
Asia/Australasia	0.04	0.17	0.08	0.16	17,352	67,759
Europe	0.19	0.00	0.77	0.90	7,269	17,746
Middle East	0.15	0.08	0.07	0.12	12,738	450,800
North America	0.12	0.37	0.11	0.14	2,727	21,365
Russia & Central Asia	0.44	0.28	0.09	0.29	7,104	10,432
South & Central America	0.03	0.00	0.45	0.20	6,152	55,351
OVERALL	0.17	0.12	0.15	0.15	59,020	689,242

Table B.44: Unspecified TRIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Unspecified TRIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.07	0.39	0.21	0.71	28,318	100,245
Asia/Australasia	0.39	0.40	1.05	1.47	104,970	79,180
Europe	0.21	0.30	0.83	2.30	20,292	12,598
Middle East	0.31	0.42	0.32	0.28	35,669	148,502
North America	0.47	0.38	1.66	1.99	33,886	56,203
Russia & Central Asia	0.32	0.20	0.37	0.98	4,893	14,218
South & Central America	0.17	0.07	1.16	1.10	14,053	13,615
OVERALL	0.31	0.37	0.74	0.94	242,083	424,563

Table B.45: Unspecified LTIR by region for companies and contractors (2025 & 2020-2024) and the number of related work hours for companies and contractors for 2025 only

Region	Unspecified LTIR				Work hours (thousands)	
	Company		Contractor		2025	
	2020-2024	2025	2020-2024	2025	Company	Contractor
Africa	0.06	0.14	0.11	0.22	28,318	100,245
Asia/Australasia	0.10	0.10	0.13	0.25	104,970	79,180
Europe	0.16	0.09	0.32	1.04	21,792	13,433
Middle East	0.10	0.11	0.08	0.11	35,669	148,502
North America	0.13	0.23	0.44	0.32	64,571	120,034
Russia & Central Asia	0.21	0.00	0.13	0.35	4,893	14,218
South & Central America	0.01	0.00	0.37	0.59	14,053	13,615
OVERALL	0.12	0.13	0.19	0.25	274,268	489,229

Section 5 Results by company

Table B.46: FAR, TRIR, and LTIR results by company (2025)

Company code 2025	FAR	TRIR		LTIR		Company only	Contractor only
	FAR total	TRIR total	Company only	Contractor only	LTIR total		
Overall	1.35	0.76	0.61	0.8	0.25	0.23	0.26
A	0.00	2.02	1.34	5.89	2.02	1.34	5.89
B	0.00	1.38	0.9	1.59	1.38	0.9	1.59
C	0.00	1.8	0	3.42	1.35	0	2.57
D	0.00	2.93	0.89	3.98	1.05	0.22	1.48
E	0.00	1.31	1.77	1.12	1.05	0.88	1.12
F	0.00	1.7	0	2.28	1.02	0	1.37
G	0.00	no data	no data	no data	0.94	0.58	1.23
H	0.00	2.13	1.62	2.34	0.91	0.62	1.04
I	2.33	1.89	1.75	1.93	0.79	0.76	0.8
J	38.87	1.07	0.66	1.4	0.78	0.66	0.87
K	0.00	3	0.22	8.81	0.75	0	2.32
L	0.46	1.13	0.37	1.31	0.61	0.34	0.68
M	0.00	1.08	0.56	1.38	0.47	0.19	0.63
N	0.00	1.32	0.88	2.04	0.47	0.32	0.71
O	2.00	1.15	0.71	1.39	0.43	0.21	0.55
P	0.00	1.61	1.25	1.69	0.42	0.44	0.42
Q	11.74	0.78	0.27	0.87	0.39	0.27	0.41
S	7.54	no data	no data	no data	0.37	0.23	0.51
T	0.00	2.05	1.53	2.21	0.36	0.51	0.32
U	1.10	1.02	0.4	1.17	0.36	0.17	0.41
V	0.00	0.65	0.62	0.66	0.32	0.22	0.34
W	2.81	1.24	0.47	1.45	0.3	0.09	0.36
X	0.00	1.32	0	1.57	0.29	0	0.35
Y	0.00	0.46	0.37	0.55	0.28	0.28	0.28
Z	0.00	1.65	0.61	2.22	0.26	0	0.4
AA	0.00	0.44	0.44	0.44	0.22	0	0.24
BB	0.00	0.76	1.07	0.71	0.21	0.38	0.17
CC	0.93	no data	no data	no data	0.19	0.34	0.07
DD	4.21	0.77	0.65	0.92	0.19	0.17	0.21
EE	0.00	0.36	0.35	0.36	0.18	0.28	0.15
FF	0.00	0.77	0.3	0.79	0.18	0.07	0.18
GG	0.69	1.41	0.92	1.53	0.14	0.11	0.15
HH	0.00	1.63	0.54	2.86	0.14	0	0.3
II	0.00	1.62	0.69	1.85	0.14	0.1	0.15
JJ	3.93	0.28	0.32	0.27	0.12	0	0.14
KK	1.70	0.54	0.22	0.64	0.12	0.07	0.13
LL	3.33	0.2	0	0.21	0.12	0	0.12
MM	0.00	0.51	0.5	0.51	0.09	0	0.12
NN	0.94	0.31	0.16	0.36	0.09	0.08	0.1
OO	0.21	0.1	0.15	0.1	0.05	0.06	0.05
PP	0.00	0.45	1.12	0.31	0.05	0	0.06
QQ	0.00	0.24	0	0.28	0.05	0	0.06
RR	2.19	0.12	0.03	0.13	0.04	0.03	0.04
SS	0.00	0.5	0	0.52	0	0	0
TT	0.00	1.32	0.34	1.81	0	0	0
UU	0.00	1.12	0	1.53	0	0	0
VV	0.00	0.31	0.33	0.29	0	0	0
WW	0.00	2.3	0	2.72	0	0	0
XX	0.00	0.19	0	0.26	0	0	0
YY	0.00	0	0	0	0	0	0
ZZ	0.00	0.54	0	0.92	0	0	0
AAA	0.00	1.02	0	1.32	0	0	0
BBB	0.00	0.47	0.58	0.44	0	0	0

Note: company codes are allocated according to company & contractor LTIR performance. In TRIR columns, "no data" indicates that a company did not report medical treatment and restricted work day cases.

Table B.47: TRIR by company and function (2025)

Company code	TRIR (2025)			
	Exploration	Drilling	Production	Construction
Overall	0.31	0.92	0.8	0.62
A	no data	5.89	1.34	no data
B	0	2.9	2.94	0
C	no data	no data	3.11	no data
D	0	5.42	2.67	7.07
E	no data	1.15	1.36	no data
F	no data	no data	no data	no data
G	no data	no data	no data	no data
H	0.38	2.07	3.4	0.67
I	no data	no data	no data	no data
J	0	2.08	1.14	1.93
K	no data	no data	3	no data
L	1.8	1.87	1.08	0.82
M	0	2.13	1.11	1.45
N	no data	1.07	1.62	2.13
O	1.04	2.28	1.67	0.81
P	1.6	2.58	1.57	0.92
Q	no data	0.82	0.9	0.55
S	no data	no data	no data	no data
T	no data	no data	2.11	no data
U	no data	no data	no data	no data
V	0	3.64	0.58	0.29
W	6.3	3.63	0.98	0.77
X	no data	1.27	no data	2.21
Y	no data	no data	0.46	no data
Z	0	0.66	3.15	1.85
AA	no data	0.45	1.13	0.34
BB	no data	no data	0.76	no data
CC	no data	no data	no data	no data
DD	no data	no data	no data	no data
EE	0	0.96	0.33	0.22
FF	no data	0.61	0.39	0.87
GG	0	1.69	1.56	0.31
HH	no data	0	3.42	3.17
II	0	2.33	1.12	2.17
JJ	0.13	1.02	0.14	0.19
KK	1.08	0.82	0.4	2
LL	no data	0.44	0.19	0.27
MM	0	0.43	0.61	0.8
NN	0	0.4	0.41	0.38
OO	0	0.27	0.1	0.02
PP	no data	no data	no data	no data
QQ	0	0	0.44	0
RR	0	0.09	0.15	no data
SS	no data	no data	0.51	no data
TT	0	no data	0.66	1.91
UU	no data	no data	1.12	no data
VV	0.33	0	no data	0
WW	no data	0	5.89	no data
XX	no data	0.31	0.3	0
YY	no data	no data	no data	no data
ZZ	no data	0	0.64	0
AAA	no data	0	1.08	no data
BBB	no data	no data	0.47	no data

Note: In TRIR columns, "no data" indicates that a company did not report medical treatment and restricted work day cases.

Table B.48: LTIR by company and function (2025)

Company code	LTIR (2025)			
	Exploration	Drilling	Production	Construction
Overall	0.11	0.3	0.31	0.15
A	no data	5.89	1.34	no data
B	0	2.9	2.94	0
C	no data	no data	2.33	no data
D	0	0	1.25	3.93
E	no data	1.15	1.02	no data
F	no data	no data	no data	no data
G	0	2.52	0.79	0
H	0	0.07	1.69	0.29
I	no data	no data	no data	no data
J	0	0	1.01	0
K	no data	no data	0.75	no data
L	0.77	1.16	0.64	0.16
M	0	0.85	0.56	0
N	no data	0.72	0.57	0.43
O	1.04	0.78	0.65	0.28
P	0	0.67	0.5	0
Q	no data	0	0.49	0.28
S	no data	no data	0.37	no data
T	no data	no data	0.37	no data
U	no data	no data	no data	no data
V	0	2.24	0.19	0.09
W	1.58	0.8	0.46	0.19
X	no data	0.25	no data	0.55
Y	no data	no data	0.28	no data
Z	0	0.66	0.55	0.13
AA	no data	0	0	0.27
BB	no data	no data	0.21	no data
CC	0.05	0.34	0.2	no data
DD	no data	no data	no data	no data
EE	0	0.28	0.26	0.06
FF	no data	0.24	0.16	0.18
GG	0	0.15	0.18	0
HH	no data	0	0.38	0
II	0	0.23	0.08	0.27
JJ	0.13	0.37	0.09	0.12
KK	1.08	0.18	0.08	0.33
LL	no data	0.44	0.04	0.21
MM	0	0.22	0.06	0.27
NN	0	0.13	0.14	0.11
OO	0	0.17	0.05	0.02
PP	no data	no data	no data	no data
QQ	0	0	0.09	0
RR	0	0.04	0.04	no data
SS	no data	no data	0	no data
TT	0	no data	0	0
UU	no data	no data	0	no data
VV	0	0	no data	0
WW	no data	0	0	no data
XX	no data	0	0	0
YY	no data	no data	no data	no data
ZZ	no data	0	0	0
AAA	no data	0	0	no data
BBB	no data	no data	0	no data

Note: In LTIR columns by function, "no data" indicates that a company did not break down data sets by that work function.

Database dimensions (Appendix A)

Table B.49: Total work hours reported (1985-2025)

Year	Work hours reported (thousands)			Participating companies
	Overall	Company	Contractor	
1985	655,650	410,409	245,241	22
1986	544,053	305,637	238,416	26
1987	602,480	355,578	246,902	30
1988	616,448	363,530	252,918	35
1989	655,945	330,970	324,975	33
1990	720,652	331,986	388,666	31
1991	940,538	441,141	499,397	36
1992	944,143	431,139	513,004	33
1993	919,176	410,474	508,702	35
1994	871,973	397,258	474,715	30
1995	840,811	355,695	485,186	30
1996	911,540	360,149	551,391	36
1997	1,161,335	389,442	771,893	40
1998	1,131,229	385,619	745,610	41
1999	1,197,460	395,141	802,319	40
2000	1,633,855	571,915	1,061,940	44
2001	1,976,646	633,039	1,343,607	41
2002	2,120,829	636,414	1,484,415	35
2003	2,247,026	663,894	1,583,132	36
2004	2,290,453	638,739	1,651,714	37
2005	2,380,670	639,292	1,741,378	39
2006	2,936,974	734,425	2,202,549	41
2007	2,912,801	667,986	2,244,815	38
2008	3,304,168	712,482	2,591,686	39
2009	3,585,842	822,240	2,763,602	43
2010	3,411,144	725,673	2,685,471	42
2011	3,456,078	753,100	2,702,978	45
2012	3,691,040	759,600	2,931,440	49
2013	3,770,546	820,856	2,949,690	50
2014	4,365,959	945,572	3,420,387	52
2015	3,719,316	896,862	2,822,454	49
2016	2,895,621	667,335	2,228,286	43
2017	2,999,039	688,779	2,310,260	45
2018	3,066,350	653,764	2,412,586	46
2019	3,038,352	657,258	2,381,094	48
2020	2,544,201	708,712	1,835,489	48
2021	2,679,026	686,668	1,992,358	50
2022	2,579,000	659,717	1,919,283	51
2023	3,291,382	881,802	2,409,580	58
2024	4,158,877	1,060,726	3,098,151	56
2025	3,854,622	906,324	2,948,298	56

Table B.50: Exposure hours by region (2024 and 2025)

Region	Hours (thousands)	
	2024	2025
Africa	478,530	394,541
Asia/Australasia	877,373	786,218
Europe	230,398	215,038
Middle East	1,170,824	1,234,235
North America	756,140	644,440
Russia & Central Asia	228,189	230,872
South & Central America	417,421	349,275
OVERALL	4,158,877	3,854,622

Table B.51: Exposure hours by function (2024 and 2025)

Function	Hours (thousands)	
	2024	2025
Exploration	55,709	75,214
Drilling	714,524	526,453
Production	1,847,122	1,741,193
Construction	804,614	748,263
Unspecified	736,907	763,497
OVERALL	4,158,877	3,854,622

Appendix C - Contributing companies

Table C.1 shows the size of the database in thousands of work hours reported for each contributing company and whether reported data include information on contractor statistics, breakdown by function, restricted work day cases, days lost following lost work day, and restricted work day cases. All company submissions include data on numbers of fatalities and lost work day cases.

Table C.1: Contributing companies 2025

Company	Hours (thousands)	Contractor data	Data by function	RWDCs	LWDC days	RWDC days
ADDAX Petroleum Limited	1,738	yes	mostly	yes	yes	yes
ADNOC	479,155	yes	mostly	yes	yes	yes
Aker BP	11,709	yes	mostly	no	partly	no
Assala Energy	6,840	yes	mostly	yes	no	no
Azule	22,863	yes	mostly	yes	yes	yes
Bapco Energies	19,840	yes	no	yes	yes	yes
Basrah Gas Company	21,638	yes	yes	yes	yes	yes
BP	70,854	yes	yes	yes	no	no
Brunei Shell	31,623	yes	mostly	yes	no	no
BW Energy	3,623	yes	partly	yes	yes	yes
CCED	6,444	yes	mostly	yes	yes	mostly
Cenovus	51,221	yes	mostly	yes	yes	yes
Chevron	213,665	yes	mostly	yes	yes	yes
ConocoPhillips	160,745	yes	yes	yes	no	no
Crescent Petroleum	9,064	yes	mostly	yes	yes	yes
Dana Gas	4,019	yes	partly	yes	yes	yes
Dolphin Energy	8,522	yes	yes	yes	yes	yes
ENI	131,585	yes	mostly	yes	yes	mostly
Equinor ASA	114,759	yes	mostly	yes	no	no
ExxonMobil	144,857	yes	mostly	yes	yes	no
Gulf Keystone	1,835	yes	yes	yes	yes	yes
Harbour Energy	14,838	yes	mostly	yes	yes	yes
INPEX Corporation	14,118	yes	partly	yes	yes	yes
Ithaca Energy	5,899	yes	no	yes	yes	yes
KMG	92,870	yes	yes	no	yes	no
Kosmos Energy	620	yes	no	yes	yes	yes
Kuwait Oil Company	152,719	yes	mostly	yes	no	no
MOL	10,290	yes	mostly	yes	yes	yes
North Oil Company	20,594	yes	mostly	yes	yes	yes
OMV	25,664	yes	mostly	yes	yes	yes
ONGC	94,940	yes	no	yes	yes	yes
Orlen	7,910	yes	yes	yes	yes	yes
Oxy	91,256	yes	no	yes	yes	yes
Pan American Energy	20,643	yes	mostly	yes	yes	yes
PEMEX	215,518	yes	mostly	no	partly	no
Perenco	42,846	yes	no	yes	partly	partly
Pertamina	320,013	yes	yes	yes	no	no
Petrobras	218,510	yes	mostly	mostly	yes	mostly
Petronas Carigali Sdn Bhd	55,371	no	mostly	yes	yes	yes
Pluspetrol	25,546	yes	mostly	yes	yes	yes
Prime Energy	1,792	yes	yes	yes	yes	yes
Prio	3,805	yes	yes	yes	yes	mostly
PTTEP	58,743	yes	mostly	yes	yes	yes
QatarEnergy	93,256	yes	mostly	yes	yes	mostly
QatarEnergy LNG	302,478	yes	mostly	yes	yes	yes
Renaissance	60,086	yes	mostly	yes	yes	yes
Repsol	13,295	yes	mostly	yes	yes	yes
Shell Companies	149,888	yes	mostly	yes	yes	yes
SOCAR	72,782	no	mostly	yes	yes	yes
Sonangol	108	no	yes	yes	yes	yes
Spirit Energy	2,226	yes	mostly	yes	yes	yes


Company	Hours (thousands)	Contractor data	Data by function	RWDCs	LWDC days	RWDC days
TotalEnergies	106,464	yes	mostly	yes	yes	no
Trident Energy	8,294	yes	mostly	yes	yes	yes
Tullow Oil	4,892	yes	yes	yes	yes	yes
Vår Energy	6,670	yes	yes	yes	yes	yes
Woodside	23,073	yes	mostly	yes	yes	yes

*Note: A data row is a single entry for a company for one country and location (one of company onshore, company offshore, contractor onshore, contractor offshore), e.g., A company, UK, company offshore.
Yes = reported for all data rows / mostly = reported for more than 50% of data rows / partly = reported for less than 50% of data rows / no = not reported at all.*

Appendix D - Countries represented


The figures and table below show the breakdown of reported hours worked in regions and countries. Also shown is the number of companies reporting data in each country. They do not necessarily show all hours worked in the exploration and production sectors of the oil and gas industry in each country.

Figure D1: Number of companies represented by country and region 2025



Iran and Russia excluded

Figure D2: Number of work hours (thousands) reported by country and region 2025



Number of reported work hours (thousands)

AFRICA		ASIA/ AUSTRALASIA		EUROPE		MIDDLE EAST		RUSSIA & CENTRAL ASIA	
Algeria	Angola	Australia	Bangladesh	Albania	Austria	Bahrain	Iraq	Azerbaijan	Georgia
18,512	77,516	68,025	4,555	211	1,480	19,840	39,016	87,389	1,915
Cameroon	Chad	Brunei	China	Bulgaria	Croatia	Israel	Kurdistan Region of Iraq	Kazakhstan	Turkmenistan
6,357	4,394	31,642	16,171	50	1,321	3,500	10,328	138,592	2,975
Congo	DRC	East Timor	India	Cyprus	Denmark	Kuwait	Oman		
36,354	3,671	2	136,382	1,216	4,474	168,974	61,351		
Egypt	Equatorial Guinea	Indonesia	Japan	France	Germany	Qatar	Turkey		
29,083	5,061	342,971	4,519	2,331	3,453	439,748	878		
Gabon	Ghana	Malaysia	Myanmar	Hungary	Italy	UAE	Yemen		
21,059	7,515	91,050	5,610	2,735	10,044	490,588	9		
Ivory Coast	Kenya	New Zealand	Pakistan	Netherlands	Norway				
3,442	312	905	6,234	8,871	97,477				
Libya	Mauritania	Papua New Guinea	Philippines	Poland	Portugal				
12,419	1,757	12,140	4,260	7,910	27				
Mozambique	Namibia	Singapore	South Korea	Romania	Spain				
4,243	853	4,226	5,022	20,349	1,209				
Nigeria	São Tomé and Príncipe	Thailand	Vietnam	Switzerland	UK				
143,134	209	49,280	684	2	51,875				
Senegal	South Africa								
1,556	88								
Tanzania	Tunisia								
506	5,112								
Uganda									
9,091									

Country represented/Not represented

NORTH AMERICA		SOUTH & CENTRAL AMERICA	
Canada	Mexico	Argentina	Bolivia
79,982	226,155	41,110	2,618
USA		Brazil	Colombia
338,302		252,647	2,706
		Ecuador	Guatemala
		1,053	836
		Guyana	Peru
		21,731	17,246
		Suriname	Trinidad and Tobago
		607	7,733
		Venezuela	
		984	

Iran and Russia excluded

Table D.1: Countries represented (2025)

Region	Country	Reporting companies (number)	Hours (thousands)
Africa	Algeria	6	18,512
Africa	Angola	6	79,804
Africa	Cameroon	2	6,357
Africa	Chad	1	4,394
Africa	Congo	4	36,354
Africa	Drc - Democratic Republic of the Congo (formerly Zaire)	1	3,671
Africa	Egypt	8	29,083
Africa	Equatorial Guinea	4	5,061
Africa	Gabon	5	21,059
Africa	Ghana	3	7,515
Africa	Ivory Coast	3	3,442
Africa	Kenya	1	312
Africa	Libya	6	12,419
Africa	Mauritania	4	1,757
Africa	Mozambique	3	4,243
Africa	Namibia	3	853
Africa	Nigeria	6	143,134
Africa	São Tomé and Príncipe	2	209
Africa	Senegal	4	1,556
Africa	South Africa	2	88
Africa	Tanzania	2	506
Africa	Tunisia	3	5,112
Africa	Uganda	1	9,091
Asia/Australasia	Australia	8	68,025
Asia/Australasia	Bangladesh	1	4,555
Asia/Australasia	Brunei	2	31,642
Asia/Australasia	China	9	16,171
Asia/Australasia	East Timor	1	2
Asia/Australasia	India	5	136,382
Asia/Australasia	Indonesia	8	345,504
Asia/Australasia	Japan	2	4,519
Asia/Australasia	Malaysia	8	91,050
Asia/Australasia	Myanmar	1	5,610
Asia/Australasia	New Zealand	1	905
Asia/Australasia	Pakistan	1	6,234
Asia/Australasia	Papua New Guinea	2	12,140
Asia/Australasia	Philippines	2	4,260
Asia/Australasia	Singapore	7	4,226
Asia/Australasia	South Korea	4	5,022
Asia/Australasia	Thailand	6	49,280
Asia/Australasia	Vietnam	3	684
Europe	Albania	2	211
Europe	Austria	1	1,480
Europe	Bulgaria	1	50
Europe	Croatia	1	1,321
Europe	Cyprus	4	1,216
Europe	Denmark	2	4,474
Europe	France	6	2,331
Europe	Germany	2	3,453
Europe	Hungary	1	2,735
Europe	Italy	5	10,044
Europe	Netherlands	5	8,871
Europe	Norway	12	97,477
Europe	Poland	1	7,910
Europe	Portugal	1	27
Europe	Romania	1	20,349
Europe	Spain	1	1,209
Europe	Switzerland	1	2
Europe	UK	20	51,875
Middle East	Bahrain	1	19,840
Middle East	Iraq	4	39,016
Middle East	Israel	1	3,500

Region	Country	Reporting companies (number)	Hours (thousands)
Middle East	Kurdistan Region Of Iraq	2	10,328
Middle East	Kuwait	3	168,974
Middle East	Oman	6	61,351
Middle East	Qatar	9	439,748
Middle East	Turkey	2	878
Middle East	UAE	12	490,588
Middle East	Yemen	1	9
North America	Canada	9	79,982
North America	Mexico	9	226,155
North America	USA	14	338,302
Russia & Central Asia	Azerbaijan	4	87,389
Russia & Central Asia	Georgia	1	1,915
Russia & Central Asia	Kazakhstan	7	138,592
Russia & Central Asia	Turkmenistan	1	2,975
South & Central America	Argentina	7	41,110
South & Central America	Bolivia	4	2,618
South & Central America	Brazil	12	252,647
South & Central America	Colombia	3	2,706
South & Central America	Ecuador	1	1,053
South & Central America	Guatemala	1	836
South & Central America	Guyana	1	21,731
South & Central America	Peru	2	17,246
South & Central America	Suriname	2	607
South & Central America	Trinidad and Tobago	5	7,733
South & Central America	Venezuela	3	984

Appendix E - Glossary of terms

Assault and violent act (as an incident/event category)

Intentional attempt, threat or act of bodily injury by a person or person(s) or by violent harmful actions of unknown intent, includes intentional acts of damage to property.

Aviation accident (as an incident/event category)

An occurrence associated with the operation of an aircraft which, in the case of a manned aircraft, takes place between the time any person boards the aircraft with the intention of flight until such time as all such persons have disembarked or, in the case of an unmanned aircraft, takes place between the time the aircraft is ready to move with the purpose of flight until such time as it comes to rest at the end of the flight and the primary propulsion system is shut down.

Caught in, under or between (as an incident/event category)

Injury where injured person is crushed or similarly injured between machinery moving parts or other objects, caught between rolling tubulars or objects being moved, crushed between a ship and a dock, or similar incidents. Also includes vehicle incidents involving a rollover.

Causal factors

See IOGP Safety data reporting users' guide.

Commentary drive

A training technique whereby the driver conducts a typical journey and, while driving, explains what hazards he/she sees or can anticipate in the road ahead, including unseen hazards, and what safe driving techniques they will or would utilize to eliminate or minimize the threat from such hazards. The driver is accompanied by a qualified instructor who assesses if the driver is employing the correct defensive driving techniques and proper seeing habits to identify and avoid driving hazards. At the end of drive, the assessor provides feedback and coaching to the driver on any areas of improvement.

Commute travel

For injury/illness reporting, Commute travel begins when the worker is seated in the vehicle in preparation for departure and ends when the worker arrives at their home or worksite and the vehicle is placed in park or taken out of gear. For MVC reporting, Commute travel begins when the worker is no longer driving on company business.

Note: Travel to and from field operations locations is considered to be company business travel.

A vehicle crash is considered to have occurred during commute travel if it meets the definition above, regardless of whether the event occurs while driving a company or personal vehicle or whether the employee or contract employee is being compensated during this time. Where appropriate, any vehicle crash occurring during Commute travel may be considered as asset or property damage but not as an MVC.

Note: All work-related travel performed by workers that are home-based, i.e., work from their place of residence, is considered to be company business travel.

Commuting

- Travel from home to first work site and travel from last work site to home.
- Travel between a worker's identified work location and any location for personal business, including a restaurant.
- Travel between a worker's established 'home away from home' to the first worksite or to any location for personal business, including a restaurant.
- Travel between home and a non-company event, e.g., local conference or other similar function.

Company employee

Any person employed by and on the payroll of the reporting company, including corporate and management personnel specifically involved in E&P. Persons employed under short-service contracts are included as company employees provided they are paid directly by the company.

Confined space (as an incident/event category)

Spaces that are considered confined because their configurations hinder the activities of employee who must enter, work in, and exit them. Confined spaces include, but are not limited to underground vaults, tanks, storage bins, manholes, pits, silos, process vessels and pipelines.

Construction (as a work function)

Major construction and fabrication activities as well as disassembly, removal and disposal (decommissioning) at the end of the facility life. Includes construction of process plant, yard construction of structures, offshore installation, hook-up and commissioning, and removal of redundant process facilities.

Construction, commissioning, decommissioning (as a type of activity)

Activities involving the construction, fabrication and installation of equipment, facilities or plant, testing activities to verify design objectives or specification, and also disassembly, removal and disposal (decommissioning) at the end of the facility life.

Contracted (vehicle)

See Owned, contracted or leased.

Contractor

A contractor is defined as an individual or organization performing work for the reporting company, following verbal or written agreement. Subcontractor is synonymous with contractor.

Contractor employee

Any person employed by a contractor or contractor's subcontractor(s) who is directly involved in execution of prescribed work under a contract with the reporting company.

Cut, puncture, scrape (as an incident/event category)

Abrasions, scratches and wounds that penetrate the skin.

Diving operations

The personnel, equipment and management systems to support a person who dives. A person dives if they enter water or any other liquid, or a chamber in which they are subject to pressure greater than 100 millibars above atmospheric pressure, and in order to survive in such an environment breathes air or other gas at a pressure greater than atmospheric pressure. Or for such a purpose uses a vehicle, capsule or suit where a sealed internal atmospheric pressure is maintained and where the external pressure differential is greater than 100 millibars.

Diving, subsea, ROV (as a type of activity)

Operations involving diving (see definition for diving operations), subsea equipment or activities and/or operations involving underwater remotely operated vehicles (ROV).

Drilling (as a work function)

All exploration, appraisal and production drilling, and workover as well as their administrative, engineering, construction, materials supply and transportation aspects. It includes site preparation, rigging up and down, and restoration of the drilling site upon work completion. Drilling includes all exploration, appraisal and production drilling.

Drilling/workover/well services (as a type of activity)

Activities involving the development, maintenance work or remedial treatments related to an oil or gas well.

Dropped objects (as an incident/event category)

Any item with the potential to cause injury, death, or equipment/environmental damage, that falls down or over from its previous position. Specifically excludes falls from height (people). Source: Dropped Object Prevention Scheme, Recommended Practice <http://www.dropsonline.org/assets/documents/DROPS-Recommended-Practice-2017.pdf>

Dropped objects (as an incident/event category)

Any item with the potential to cause injury, death, or equipment/environmental damage, that falls down or over from its previous position. Specifically excludes falls from height (people). Source: Dropped Object Prevention Scheme, Recommended Practice. <https://www.dropsonline.org/assets/documents/DROPS-Recommended-Practice-Mar2020Rev2.pdf>

Event

An unplanned or uncontrolled outcome of a business operation or activity that has or could have contributed to an injury or physical damage or environmental damage.

Excavation, trenching, ground disturbance (as a type of activity)

Work that involves a cut, cavity, trench or depression in the earth's surface formed by earth removal.

Exploration (as a work function)

Geophysical, seismographic and geological operations, including their administrative and engineering aspects, construction, maintenance, materials supply, and transportation of personnel and equipment (excluding drilling).

Explosion or Burn (as an incident/event category)

Burns or other effects of fires, explosions and extremes of temperature. 'Explosion' means a rapid combustion, not an overpressure.

Exposure: Electrical (as an incident/event category)

Exposure to electrical shock or electrical burns etc.

Exposure: Noise, Chemical, Biological, Vibration (as an incident/event category)

Exposure to noise, chemical substances (including asphyxiation due to lack of oxygen not associated with a confined space), hazardous biological material, vibration or radiation.

Falls from height (as an incident/event category)

A person falls from one level to another or event is related to work at height.

Fatal Accident Rate (FAR)

The number of company/contractor fatalities per 100 000 000 (100 million) hours worked.

Fatal incident rate (FIR)

The number of incidents that result in one or more fatalities per 100 million hours worked.

Fatality

Cases that involve one or more people who died as a result of a work-related incident.

Fatigue (as a causal factor)

Person(s) involved were mentally tired for whatever reason e.g., excessive work hours, shift patterns, staffing levels insufficient, ill-health etc. The loss of situational awareness, task fixation, distraction, and mental fatigue due to sleep loss are examples of conditions that apply to this causal factor.

First Aid Case

Cases that are not sufficiently serious to be reported as medical treatment or more serious cases but nevertheless require minor first aid treatment, e.g., dressing on a minor cut, removal of a splinter from a finger. First aid cases are not recordable incidents.

High Potential Event

A high potential event is an event which could have, under slightly different circumstances, realistically resulted in a fatal incident.

Home away from home

When travelling, workers establish a 'home away from home' when checked into a hotel, motel, or other similar temporary residence.

Travel directly to the temporary residence before check-in from the airport (train station, etc.) or rental car agency and travel direct from home to the temporary residence is considered business travel, when on work-related business.

Travel home directly from the temporary residence after checkout to the airport (train station, etc.) or rental car agency and travel direct to home from the temporary residence is considered business travel, when on work-related business.

Company mandated accommodation is not considered to be home away from home. This is considered to be a field operations location therefore travel to and from such locations is considered to be company business travel and not a commute.

Hours Worked

The actual hours worked, including overtime hours, are recorded in the case of onshore operations. The hours worked by an individual will generally be about 2,000 per year. For offshore workers, the hours worked are calculated on a 12-hour work day. Consequently, average hours worked per year will vary from 1,600 to 2,300 hours per person depending upon the on/off shift ratio. Vacations and leave are excluded.

Hours Worked in Year (thousands)

Hours are rounded to the nearest thousand.

Incident

An unplanned or uncontrolled Event or chain of Events that has resulted in at least one fatality, recordable injury, or physical or environmental damage.

Key performance indicators (KPI)

Information or data that provides evidence of a Company's performance in managing its key risks. KPIs may also be referred to as performance metrics. In the Safety Performance Indicators report, these include: number of fatalities, fatal accident and incident rates, lost time injury rate and total recordable injury rate.

Lifting, crane, rigging, deck operations (as a type of activity)

Activities related to the use of mechanical lifting and hoisting equipment, assembling and disassembling drilling rig equipment and drill pipe handling on the rig floor.

Lost Time Injury (LTI)

A fatality or lost work day case. The number of LTIs is the sum of fatalities and lost work day cases.

Lost time injury rate (LTIR)

The number of lost time injuries (fatalities + lost work day cases) per 1,000,000 hours worked.

Lost Work Day Case (LWDC)

Any work-related injury, other than a fatal injury, which results in a person being unfit for work on any day after the day of occurrence of the occupational injury. "Any day" includes rest days, weekend days, leave days, public holidays or days after ceasing employment.

LWDC severity

The average number of lost days per lost work day case.

Maintenance, inspection and testing (as a type of activity)

Activities related to preserving, repairing, examining and function testing assets, equipment, plant or facilities.

Manual handling

Use of human force to lift, lower, push, pull, carry, hold, or restrain an object.

Medical Cause of Death

This is the cause of death given on the death certificate. Where two types of causes are provided, such as "pulmonary oedema" caused by "inhalation of hot gases from a fire", both are recorded.

Medical Treatment Case (MTC)

Cases that are not severe enough to be reported as lost work day cases or restricted work day cases but are more severe than requiring simple first aid treatment.

Motor Vehicle Crash (MVC)

A work-related motor vehicle incident, e.g., collision or other event, which resulted in vehicle damage, or vehicle rollover, or personal injury, or fatality.

Note: Contractor Motor Vehicle Crash includes any vehicle operated by a contractor or subcontractor while performing work on behalf of the company, where injuries, kilometres driven, or hours worked should be recorded (e.g., delivery/courier services are excluded).

Near Miss

An unplanned or uncontrolled event or chain of events that has not resulted in recordable injury or physical damage or environmental damage but had the potential to do so in other circumstances.

Number of days unfit for work

The sum total of calendar days (consecutive or otherwise) after the days on which the occupational injuries occurred, where the persons involved were unfit for work and did not work.

Number of Employees

Average number of full-time and part-time employees involved in exploration and production, calculated on a full-time basis, during the reporting year. For example 2 part time employees each working 20 - 30 hours per week is equivalent to 1 full time employee.

Number of Fatalities

The total number of Company employees and/or Contractor employees who died as a result of an incident. Delayed deaths that occur after the incident are included if the deaths were a direct result of the incident. For example, if a fire killed one person outright, and a second died three weeks later from lung damage caused by the fire, both are reported.

Occupational Illness

Any abnormal condition or disorder, or any fatality other than one resulting from an occupational injury, caused by exposure to environmental factors associated with employment. Occupational illness may be caused by inhalation, absorption, ingestion of, or direct contact with the hazard, as well as exposure to physical and psychological hazards. It will generally result from prolonged or repeated exposure. Refer to IOGP/IPIECA Report 393 - Health Performance Indicators.

Occupational Injury

Any bodily harm such as a cut, sprain, fracture, amputation, respiratory distress, etc., which results from a work-related activity or from an exposure involving a single incident in the work environment, such as deafness from explosion, respiratory or skin symptoms from one-time chemical exposure, back disorder from a slip/trip, insect or snake bite, or electric shock.

Office, warehouse, accommodation, catering (as a type of activity)

Activities related to work conducted in offices, warehouses, workshops, accommodation and catering facilities.

Officially declared [From API RP 754]

A declaration by a recognized community official (e.g. fire, police, civil defence, emergency management) or delegate (e.g. Company official) authorized to order the community action (e.g. shelter-in-place, evacuation).

Off-road

A route used for access to places which are not accessible by a road, (see 'Road').

Offshore Work

All activities and operations that take place at sea, including activities in bays, in major inland seas, such as the Caspian Sea, or in other inland seas directly connected to oceans. Incidents including transportation of people and equipment from shore to the offshore location, either by vessel or helicopter, should be recorded as "offshore".

Onshore Work

All activities and operations that take place within a landmass, including those on swamps, rivers and lakes. Land-to-land aircraft operations are counted as onshore, even though flights are over water.

Other (as an incident/event category)

Used to specify where an incident cannot be logically classed under any other category. In the case of incident activities, includes air transport incidents.

Overexertion or Strain (as an incident/event category)

Physical overexertion, e.g., muscle strain.

Permanent Impairment (PI)

A direct work-related injury outcome that prevents a return to the person's previous (pre-incident) whole person function within 180 days as a result of an acute, single incident resulting in any of the following:

- Permanent loss of body parts
- Permanent reduction of organ's physiological function
- Permanent reduction in skin and musculoskeletal function
- Permanent reduction in psychological, social, or cognitive function

Pressure Release (as an incident/event category)

Release of gas, liquid or object under pressure from a pressurized system.

Production (as a work function)

Petroleum and natural gas producing operations, including their administrative and engineering aspects, minor construction, repairs, maintenance and servicing, materials supply, and transportation of personnel and equipment. It covers all mainstream production operations including wireline. Gas processing activities with the primary intent of producing gas liquids for sale including:

- work on production wells under pressure
- oil (including condensates) and gas extraction and separation (primary production)
- heavy oil production where it is inseparable from upstream (i.e. stream assisted gravity drainage) production
- primary oil processing (water separation, stabilization)
- primary gas processing (dehydration, liquids separation, sweetening, CO₂ removal)
- floating storage units (FSUs) and sub-sea storage units
- gas processing activities with the primary intent of producing gas liquids for sale
 - secondary liquid separation (i.e. natural gas liquids [NGL] extraction using refrigeration processing)
 - liquefied natural gas (LNG) and gas to liquids (GTL) operations
- flow-lines between wells and pipelines between facilities associated with field production operations
- oil and gas loading facilities including land or marine vessels (trucks and ships) when connected to an oil or gas production process
- pipeline operations (including booster stations) operated by company E&P business.

Production excludes:

- production drilling or workover
- mining processes associated with the extraction of heavy oil tar sands
- heavy oil when separable from upstream operations
- secondary heavy oil processing (upgrader)
- refineries.

Production operations (as a type of activity)

Activities related to the extraction of hydrocarbons from source such as an oil or gas well or hydrocarbon bearing geological structure, including primary processing, storage and transport operations. Includes normal, start-up or shut-down operations.

Recordable

A type of event, incident, injury, release or other outcome which has been determined to meet or exceed definitions, criteria or thresholds for inclusion and classification in reported data.

Restricted Work Day Case (RWDC)

Any work-related injury other than a fatality or lost work day case which results in a person being unfit for full performance of the regular job on any day after the occupational injury. Work performed might be:

- An assignment to a temporary job.
- Part-time work at the regular job.
- Working full-time in the regular job but not performing all the usual duties of the job.

Where no meaningful restricted work is being performed, the incident is recorded as a lost work day case (LWDC).

Road

A thoroughfare which has a prepared, graded and levelled surface designed for the conveyance of motor vehicles (see also 'off-road'), such as:

- Asphalt, tarmac
- Concrete
- Aggregate
- Dirt/sand
- Ice

RWDC Severity

The average number of days of restricted work per restricted work day case.

Sabotage

Deliberately destroy, damage, or obstruct (something).

Seismic/survey operations (as a type of activity)

Activities relating to the determination of sub-surface structures for the purpose of locating oil and gas deposits including geophysical and seismic data acquisition.

Slips and Trips (at the same height) (as an incident/event category)

Slips, trips and falls caused by falling over or onto something at the same height.

Struck By (as an incident/event category)

Incidents/events where injury results from being hit by moving equipment and machinery, or by flying or falling objects. Also includes vehicle incidents where the vehicle is struck by or struck against another object.

Third Party [From API RP 754]

Any individual other than an employee, contractor or subcontractor of the Company, e.g. visitors, non-contracted delivery drivers, residents.

Total recordable injuries

The sum of fatalities, lost work day cases, restricted work day cases and medical treatment cases.

Total recordable injury rate (TRIR)

The number of recordable injuries (fatalities + lost work day cases + restricted work day cases + medical treatment cases (MTC)) per million hours worked. Note when MTC or RWDC are not reported by a company for a country the associated work hours, fatalities, lost work day cases, restricted work day cases and medical treatment cases are excluded from TRIR calculations.

Transport – Air (as a type of activity)

Involving aircraft, either fixed wing or helicopters. Injuries caused by accidents on the ground at airports are classified in one of the other categories.

Transport – Land (as a type of activity)

Involving motorized vehicles designed for transporting people and goods over land, e.g., cars, buses, trucks. Pedestrians struck by a vehicle are classified as land transport incidents. Incidents from a mobile crane would only be land transport incidents if the crane was being moved between locations.

Transport - Water, including Marine Activity (as a type of activity)

Involving vessels, equipment or boats designed for transporting people and goods over water (including inland, marine, ice roads and marsh/swamp), e.g., supply vessels, crew boats.

Unspecified – Other (as a type of activity)

Incidents that cannot be logically classed under other headings or where the activity is unknown.

Unspecified (as a work function)

Unspecified is used for the entry of data associated with office personnel whose work hours and incident data cannot be reasonably assigned to the administrative support of one of the function groupings of exploration, drilling, production or construction. Corporate overhead support personnel, such as finance or human resources staff, may be examples where work hours cannot be specifically assigned to a particular function. All other data that are not separated out by function are reported as unspecified. NOTE: Data for companies that did not split their data submission by work function are included in the 'unspecified' function.

Unspecified (in general)

Unless otherwise defined, data are categorized as unspecified where the requested breakdown is not available. No data provided.

Water related/drowning (as an incident/event category)

Incidents/events in which water played a significant role including drowning.

Wilful damage

Wilful or malicious damage or destruction of the property of another.

Work-Related Injury

See Occupational Injury.

IOGP safety performance indicators - 2025 data summarizes the safety performance of Member Companies participating in the data collection programme. 3.9 billion work hours of data from 56 companies were analysed according to the following key performance indicators:

- number of fatalities
- fatal accident and incident rates
- total recordable injury rate, and
- lost time injury rate.

<https://data.iogp.org>

IOGP Headquarters

3 Moorgate Place, London, EC2R 6EA, United Kingdom
T: +44 20 4570 6879
E: reception@iogp.org

IOGP Europe

T: +32 2 882 16 53
E: reception-europe@iogp.org

www.iogp.org